From: McNutt, Jan (HQ-MC000)
Sent: Monday, November 24, 2008 1:48 PM
To: Borda, Gary G. (HQ-MC000); Rotella, Robert F. (HQ-MA000)
Subject: FW: Emailing: newsdetail

████████████████████████ (b)(5)

-----Original Message-----
From: Mike Abernathy [██████████████████] (b)(6)
Sent: Monday, November 24, 2008 1:09 PM
To: McNutt, Jan (HQ-MC000)
Cc: FEIN, EDWARD K. (JSC-HA) (NASA); ███████████████████████
████████████████ (b)(6)
Subject: Emailing: newsdetail

Privileged and Confidential

This is just an FYI regarding Optima's patent trolling.

Jan,

From this it appears Honeywell may have paid Optima to attack Universal Avionics in order to
help Honeywell in their suit with UA.

Shortcut to: http://www.uasc.com/marketing/newsdetail.asp?newsid=119

But that clearly backfired and both Honeywell and Adams lost to UA.

http://www.uasc.com/marketing/newsdetail.asp?newsid=115

This makes much more sense in light of these two stories.

Mike Abernathy

RIS

From: McNutt, Jan (HQ-MC000)
Sent: Thursday, January 29, 2009 10:41 AM
To: Hammerle, Kurt G. (JSC-AL)
Cc: Fein, Edward K. (JSC-AL); Rotella, Robert F. (HQ-MA000); Borda, Gary G. (HQ-MC000)
Subject: Margolin Patent Infringement Claim

██████████████
████████████████████████████████████] (b) (5)

Margolin Claim   Margolin Claim   SBIR Margolin
20030607.pdf   20030617.pdf   Claim.pdf

Jan S. McNutt
Senior Attorney (Commercial)
Office of the General Counsel
NASA Headquarters
████████████████████████   (b)(6)
█████████████

Jed Margolin

June 7, 2003

Mr. Alan J. Kennedy
Office of the General Counsel
National Aeronautics and Space Administration
Mail Code GP, 300 E Street, S.W.
Washington DC USA 20546
Fax: 202-358-4341

Dear Mr. Kennedy,

Mr. Barry Gibbens of your Langley Research Center suggested I contact you. I missed you when I called on Friday so I am sending this fax to provide background.

I believe that NASA may have used one or more of my patents in connection with the X-38 project and may be using one or more of my patents in other projects using Synthetic Vision.

This fax contains a number of Internet links. If you would like an email version of this fax containing active links please send me an email (jm@jmargolin.com) with your email address.

Summary

In Synthetic Vision (NASA's term), the aircraft's position and orientation are used with a terrain database (such as the Digital Elevation Database) to produce a 3D projected view of the terrain over which the aircraft is flying. One of the advantages of this system is that the pilot is able to "see" the terrain regardless of weather conditions or whether it is day or night.

My U.S. Patent that pertains to this use of synthetic vision is: **U.S. Patent 5,566,073 Pilot Aid Using a Synthetic Environment** issued October 15, 1996 to Margolin. (I am the inventor and owner of the patent.) The patent application was filed August 9, 1995, and was a continuation of Application Ser. No. 08/274,394, filed July 11, 1994.

With synthetic vision it is not necessary for the pilot to be in the aircraft. I believe the X-38 project used this method.

My U.S. Patent that pertains to this use of synthetic vision is: **U.S. Patent 5,904,724 Method and Apparatus For Remotely Piloting an Aircraft** issued May 18, 1999 to Margolin. (I am the inventor and owner of the patent.) The patent application was filed January 19, 1996.

X-38 Project

I became aware that NASA was using synthetic vision in the X-38 project in the January 2003 issue of NASA Tech Briefs, page 40, **"Virtual Cockpit Window" for a Windowless Aerospacecraft.** The article is available at: http://www.nasatech.com/Briefs/Jan03/MSC23096.html

This led me to Rapid Imaging Software, Inc. and their press release (http://www.landform.com/pages/PressReleases.htm) which states:

> "On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as 'the best seat in the house', the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight."

The RIS press release provided a link to an article in Aviation Week & Space Technology: http://www.aviationnow.com/avnow/news/channel_space.jsp?view=story&id=news/sx381211.xml

As a result of more searching I have discovered a link to a Johnson Space Center SBIR Phase II award to Rapid Imaging Systems at http://sbir.gsfc.nasa.gov/SBIR/successes/ss/9-058text.html .

It includes a particularly relevant paragraph:

> The Advanced Flight Visualization Toolkit (VisualFlight™) project is developing a suite of _virtual reality immersive telepresence_ software tools which combine the real-time flight simulation abilities with the data density of a Geographic Information System (GIS). This technology is used for virtual reality training of crews, analysis of flight test data, and as an on-board immersive situation display. It will also find application as a virtual cockpit, and in _teleoperation of remotely piloted vehicles._

{The emphasis on teleoperation of remotely piloted vehicles is mine.}

A search of the SBIR archive shows the following entries.

For 2001 Phase I:
Rapid Imaging Software, Inc.
▆▆▆▆▆▆▆▆▆▆▆▆▆▆▆▆ (b) (6)
Mike Abernathy ▆▆▆▆▆▆▆
01 H6.02-8715 JSC
Integrated Video for Synthetic Vision Systems

For 2001 Phase II:
Rapid Imaging Software, Inc.
▆▆▆▆▆▆▆▆▆▆▆▆▆▆ (b)(6)
▆▆▆▆▆▆▆▆▆▆

My U.S. Patent that pertains to this use of synthetic vision is: **U.S. Patent 5,904,724 Method and Apparatus For Remotely Piloting an Aircraft** issued May 18, 1999 to Margolin. (I am the inventor and owner of the patent.) The patent application was filed January 19, 1996.

The patent can be downloaded from the UPTO Web site (www.uspto.gov) in html (no drawings) or in an odd tif format (with the drawings) that requires a special viewer.

An easier way to view and download the patent is through my Web site, on which I have posted the patent in PDF format. The link is http://www.jmargolin.com/patents2/rpv.htm .

While I have no way of knowing exactly what method(s) NASA used in controlling the X-38 (unless you are willing to make a full disclosure) my patent covers techniques as exemplified by claim 1.

1. A system comprising:

a remotely piloted aircraft including,

a position determining system to locate said remotely piloted aircraft's position in three dimensions; and

an orientation determining system for determining said remotely piloted aircraft's orientation in three dimensional space;

a communications system for communicating flight data between a computer and said remotely piloted aircraft, said flight data including said remotely piloted aircraft's position and orientation, said flight data also including flight control information for controlling said remotely piloted aircraft;

a digital database comprising terrain data;

said computer to access said terrain data according to said remotely piloted aircraft's position and to transform said terrain data to provide three dimensional projected image data according to said remotely piloted aircraft's orientation;

a display for displaying said three dimensional projected image data; and

a set of one or more remote flight controls coupled to said computer for inputting said flight control information, wherein said computer is also for determining a delay time for communicating said flight data between said computer and said remotely piloted aircraft, and wherein said computer adjusts the sensitivity of said set of one or more remote flight controls based on said delay time.

Although the X-38 project has been canceled, the methods developed to fly it are too good to waste and should be used in follow-up projects like CRV.

Synthetic Vision

I became aware of NASA's Synthetic Vision program perhaps two years ago from a program on NASA TV. I was unable to follow it up at that time due to health problems and the demands of my other patenting activity.

According to the NASA Aviation Safety Program Web site (http://avsp.larc.nasa.gov/program_svs.html)

Synthetic Vision Systems

TECHNOLOGY WOULD REDUCE AIRLINE FATALITIES
Synthetic Vision would give pilots clear skies all the time

A revolutionary cockpit display system being developed with seed money from NASA would help prevent the world's deadliest aviation accidents.

And I agree.

My U.S. Patent that pertains to this use of synthetic vision is: **U.S. Patent 5,566,073 Pilot Aid Using a Synthetic Environment** issued October 15, 1996 to Margolin. (I am the inventor and owner of the patent.) The patent application was filed August 9, 1995, and was a continuation of Application Ser. No. 08/274,394, filed July 11, 1994.

The patent can be downloaded from the USPTO Web site (www.uspto.gov) in html (no drawings) or in an odd tif format (with the drawings) that requires a special viewer.

The patent can also be downloaded from my Web site in PDF format at:
http://www.jmargolin.com/patents2/pilot.htm

As with the X-38 program I have no way of knowing exactly what method(s) NASA used in its Synthetic Vision program (unless you are willing to make a full disclosure). My patent covers techniques as exemplified by claim 1.

1. A pilot aid which uses an aircraft's position and attitude to transform data from a digital data base to present a pilot with a synthesized three dimensional projected view of the world comprising:

a position determining system for locating said aircraft's position in three dimensions;

a digital data base comprising terrain data, said terrain data representing real terrestrial terrain as at least one polygon, said terrain data generated from elevation data of said real terrestrial terrain;

an attitude determining system for determining said aircraft's orientation in three dimensional space;

a computer to access said terrain data according to said aircraft's position and to transform said terrain data to provide three dimensional projected image data according to said aircraft's orientation; and

a display for displaying said three dimensional projected image data.

NASA's Visits to My Web Site

There is good reason to believe that NASA was aware of my work in these areas through visits to my Web site. NASA has been visiting my Web site (www.jmargolin.com) regularly since I started it in December 2000. (I have no objection to NASA's visits; I am flattered that NASA considers my Web site worth visiting.)

A listing of NASA access statistics follows the end of this fax.

I also have regular visits from http://cap.nipr.mil, which I understand is a secure gateway to other military networks. I don't know if NASA uses nipr so I have not included it in my listing.

The Web Statistics software provided by my Web Hosting Service tell me who is visiting my Web site and what people are looking at but not who is looking at what. (In January of this year I discovered there are raw Web log files containing this information but my Web Hosting Service does not keep backup log files older than the previous month.)

I am including an example of the detailed Web log data; it's understandable why my Web Hosting Service abstracts it into a less detailed form.

The article being referenced is **Unit Vector Math for 3D Graphics** (www.jmargolin.com/uvmath/uvmenu.htm)

Now that I can see what people are looking at I have noticed a great deal of interest in this article as well as **The Relationship between Unit Vector Rotations and Euler Angle Functions** . (www.jmargolin.com/uvmath/euler.doc)

These articles also seem to interest military contractors like Lockheed Martin (lmco.com), Boeing (boeing.com), Northrop Grumman (northgrum.com), and SAIC (saic.hq.nasa.gov) as well as a large number of educational institutions.

Some accesses are obviously just for fun, to articles such as to **Gas Music From Jupiter** (www.jmargolin.com/gmfj/gmfj.htm)

There are also visits from most of our national labs. I expect they are interested in **U.S. Patent 6,377,436 Microwave Transmission Using a Laser-Generated Plasma Beam Waveguide** issued April 23, 2002 to Jed Margolin.

Abstract

A directed energy beam system uses an ultra-fast laser system, such as one using a titanium-sapphire infrared laser, to produce a thin ionizing beam through the atmosphere. The beam is moved in either a circular or rectangular fashion to produce a conductive shell to act as a waveguide for microwave energy. Because the waveguide is produced by a plasma it is called a plasma beam waveguide. The directed energy beam system can be used as a weapon, to provide power to an unmanned aerial vehicle (UAV) such as for providing communications in a cellular telephone system, or as an ultra-precise radar system.

There is a possibility that this device could be used to make a linear Tokamak. (www.jmargolin.com/debs/debs.htm)

Conclusion

I realize this is a great deal of material to wade through, but I would appreciate confirmation that you have received it and, if possible, an estimate as to when I can expect to hear NASA's decision on this claim.

Hopefully, then we can discuss compensation. The '724 patent is available for sale if NASA wishes to purchase it to avoid setting the precedent of the U.S. Government paying compensation for each flight of an aircraft using my patent. (I don't think this would be popular with DOD.) I expect that the first UAV to crash due to Pilot Induced Oscillation (or just Flight Computer Induced Oscillation, as occurred in the first flight of the Predator) would cost more than the cost of buying my patent. I believe this patent also has commercial applications like using UAVs for traffic reporting and in Law Enforcement so your Commercialization Department may be able to generate income with it.

Sincerely yours,

Jed Margolin

Jed Margolin

~~[redacted]~~ (b)(6)

Here are NASA's visits to my Web site:

June 2001
nasa.gov

Total hits	Files	Pageview	Bytes sent		Hostname
2 0.02%	1	2	73232	0.02%	dhcp161-117.hst.nasa.gov

July 2001
nasa.gov

Total hits	Files	Pageview	Bytes sent		Hostname
24 0.27%	24	1	216909	0.08%	aavigill.wff.nasa.gov
1 0.01%	1	1	96274	0.04%	antonius-dekorte-pc.jpl.nasa.gov
25 0.28%	25	2	313183	0.11%	

August 2001
nasa.gov

Total hits	Files	Pageview	Bytes sent		Hostname

Total hits		Files	Pageview	Bytes sent		Hostname
40	0.38%	40	1	184514	0.06%	time2burn.larc.nasa.gov
24	0.23%	24	1	216909	0.07%	gerhard.gsfc.nasa.gov
64	0.61%	64	2	401423	0.12%	

October 2001
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
1	0.01%	1	1	549657	0.11%	halljm.nsstc.nasa.gov

November 2001
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
48	0.39%	24	2	216909	0.06%	aavigill.wff.nasa.gov
42	0.34%	42	1	532111	0.14%	mac01291100705.jpl.nasa.gov
1	0.01%	1	1	21505	0.01%	dhcp-78-14-233.jpl.nasa.gov
91	0.73%	67	4	770525	0.21%	

December 2001
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
1	0.01%	1	1	90494	0.01%	pgrant.arc.nasa.gov

February 2002
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
1	0.01%	1	0	120832	0.03%	csmad-nt-23.jpl.nasa.gov
1	0.01%	1	1	504805	0.11%	cielo2k.jpl.nasa.gov
2	0.01%	2	1	625637	0.13%	

March 2002
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
58	0.35%	45	5	319389	0.05%	fantasy.arc.nasa.gov
6	0.04%	5	4	1299302	0.22%	fryepc.larc.nasa.gov
1	0.01%	1	0	120832	0.02%	shum.larc.nasa.gov

65 0.39%	51	9	1739523 0.29%	

April 2002
nasa.gov

Total hits	Files	Pageview	Bytes sent	Hostname
40 0.23%	40	1	184514 0.03%	cevennes.jpl.nasa.gov
7 0.04%	7	2	45302 0.01%	doppler.jpl.nasa.gov
1 0.01%	1	1	5735 0.00%	math.jpl.nasa.gov
1 0.01%	1	0	120832 0.02%	k-137-78-152-182.jpl.nasa.gov
49 0.29%	49	4	356383 0.06%	

May 2002
nasa.gov

Total hits	Files	Pageview	Bytes sent	Hostname
4 0.02%	0	0	0 0.00%	k1505776.ksc.nasa.gov
1 0.00%	1	0	120832 0.02%	manzanita-227-215.arc.nasa.gov
1 0.00%	1	1	96274 0.02%	seraph3.lerc.nasa.gov
6 0.03%	2	1	217106 0.03%	

June 2002
nasa.gov

Total hits	Files	Pageview	Bytes sent	Hostname
3 0.02%	1	1	96694 0.02%	micronovich.gsfc.nasa.gov

July 2002
nasa.gov

Total hits	Files	Pageview	Bytes sent	Hostname
43 0.19%	43	4	190275 0.03%	seraph3.lerc.nasa.gov
42 0.19%	42	3	189552 0.03%	varies01113104503.jpl.nasa.gov
2 0.01%	2	2	7802 0.00%	paulafinlayson-pc-pentium.jpl.nasa.gov
1 0.00%	1	1	350096 0.06%	brodbell1.gsfc.nasa.gov
1 0.00%	1	1	93686 0.02%	poes12.gsfc.nasa.gov
89 0.39%	89	11	831411 0.14%	

August 2002
nasa.gov

Total hits	Files	Pageview	Bytes sent	Hostname
24 0.11%	24	1	216909 0.03%	envision.arc.nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
1	0.00%	1	1	90494	0.01%	pc02141110149.jpl.nasa.gov
1	0.00%	1	1	142144	0.02%	tizzie.nsstc.nasa.gov
26	0.12%	26	3	449547	0.06%	

September 2002

nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
5	0.02%	1	0	121528	0.02%	knepper.ivv.nasa.gov
1	0.00%	1	0	285696	0.04%	seraph2.lerc.nasa.gov
1	0.00%	1	0	120832	0.02%	webproxy2.dfrc.nasa.gov
7	0.03%	3	0	528056	0.08%	

October 2002

nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
98	0.45%	98	14	827297	0.11%	dial37.jsc.nasa.gov
1	0.00%	1	1	49690	0.01%	isdn-dial-050.gsfc.nasa.gov
1	0.00%	1	0	120832	0.02%	latema.jpl.nasa.gov
1	0.00%	1	0	285696	0.04%	dkiewicz-pc.jpl.nasa.gov
101	0.47%	101	15	1283515	0.16%	

November 2002

nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
27	0.12%	25	1	506284	0.06%	ntserve.gdscc.nasa.gov
7	0.03%	7	2	45342	0.01%	ecn1950165.gsfc.nasa.gov
2	0.01%	2	2	1155686	0.15%	zebra.arc.nasa.gov
1	0.00%	1	1	350096	0.04%	norton.gsfc.nasa.gov
37	0.17%	35	6	2057408	0.26%	

December 2002

nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
7	0.03%	7	2	45269	0.01%	ws196.gsfc.nasa.gov

January 2003

nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname

2	0.01%	2	2	29129	0.00%	csg-	686.cdscc.nasa.gov

February 2003
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
2	0.01%	2	2	29138	0.00%	odinssc609337.ssc.nasa.gov

April 2003
nasa.gov

Total hits		Files	Pageview	Bytes sent		Hostname
40	0.17%	40	1	184514	0.02%	khgmac.larc.nasa.gov
8	0.03%	5	4	40212	0.00%	kid-emillerw2k.saic.hq.nasa.gov
5	0.02%	1	0	121528	0.01%	psycho.larc.nasa.gov
4	0.02%	3	3	63471	0.01%	b03042144127.jpl.nasa.gov
3	0.01%	3	3	29881	0.00%	seraph2.grc.nasa.gov
60	0.25%	52	11	439606	0.05%	

Example of Detailed Web Log Data

This is an example of the detailed Web log data, so it's understandable why my Web Hosting Service abstracts it into a less detailed form.

The article being referenced is Unit Vector Math for 3D Graphics (www.jmargolin.com/uvmath/uvmenu.htm)

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/fig1.gif HTTP/1.1" 200 2590
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m1.gif HTTP/1.1" 200 2237
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m2.gif HTTP/1.1" 200 1464
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m3.gif HTTP/1.1" 200 715
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m4.gif HTTP/1.1" 200 1720
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500]   "GET /uvmath/m5.gif HTTP/1.1" 200 1738 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m7.gif HTTP/1.1" 200 1549 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m8.gif HTTP/1.1" 200 1939 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m6.gif HTTP/1.1" 200 1762 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m9.gif HTTP/1.1" 200 4152 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m10.gif HTTP/1.1" 200 2732 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m11.gif HTTP/1.1" 200 2572 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m12.gif HTTP/1.1" 200 2580 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m13.gif HTTP/1.1" 200 3915 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m14.gif HTTP/1.1" 200 2591 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m15.gif HTTP/1.1" 200 2224 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m16.gif HTTP/1.1" 200 1858 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m17.gif HTTP/1.1" 200 1742 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500]   "GET /uvmath/m18.gif HTTP/1.1" 200 2642
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m19.gif HTTP/1.1" 200 1738
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m20.gif HTTP/1.1" 200 1762
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:14 -0500] "GET /uvmath/m21.gif HTTP/1.1" 200 1696
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m22.gif HTTP/1.1" 200 2224
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m23.gif HTTP/1.1" 200 1858
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m24.gif HTTP/1.1" 200 1711
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/fig6.gif HTTP/1.1" 200 3304
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/fig7.gif HTTP/1.1" 200 995
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/fig8.gif HTTP/1.1" 200 4441
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/fig11.gif HTTP/1.1" 200 3186
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/fig12.gif HTTP/1.1" 200 3743
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/fig14.gif HTTP/1.1" 200 1936
"http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0;
Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500]   "GET /uvmath/fig16.jpg HTTP/1.1" 200 61706 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m25.gif HTTP/1.1" 200 1358 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m26.gif HTTP/1.1" 200 1413 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m27.gif HTTP/1.1" 200 1052 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m28.gif HTTP/1.1" 200 1017 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m29.gif HTTP/1.1" 200 1673 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:15 -0500] "GET /uvmath/m30.gif HTTP/1.1" 200 2224 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:24 -0500] "GET /uvmath/uvmath.htm HTTP/1.1" 200 40231 "http://www.google.com/search?q=+%22euler+angle%22+normal+openGL&hl=en&lr=&ie=UTF-8&oe=UTF-8&start=10&sa=N" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

khgmac.larc.nasa.gov - - [01/Apr/2003:09:32:24 -0500] "GET /uvmath/fig3.gif HTTP/1.1" 200 2524 "http://www.jmargolin.com/uvmath/uvmath.htm" "Mozilla/4.0 (compatible; MSIE 6.0; Windows NT 5.0; Q312461; .NET CLR 1.0.3705)"

---end

Mr. Alan J. Kennedy
Director, Infringement Division
Office of the Associate General Counsel
National Aeronautics and Space Administration
Headquarters

(b)(6)

Attn: GP(02-37016)

Dear Mr. Kennedy,

I have received your letter dated June 11, 2003.

In my contacts with NASA personnel I have repeatedly stressed my desire that this matter be resolved in a friendly manner. However, since NASA has rejected my request to consider a license proffer and in view of your letter of June 11, it is clear that NASA has decided to handle this in an adversarial manner.

Before I respond to your letter in detail, I want to make things easier for me by withdrawing my U.S. Patent **5,566,073** *Pilot Aid Using a Synthetic Environment* from this administrative claim in order to focus more directly on NASA's infringement of my U.S. Patent **5,904,724** *Method and Apparatus For Remotely Piloting an Aircraft* . However, I reserve the right to file a claim concerning the '073 patent at a later time.

(1)   The identification of all claims of the patent(s) alleged to be infringed.

As I stated in my email of May 13, 2003 to Mr. Hammerle of LARC and in my fax of June 7, 2003 to you, I have no way of determining exactly which claims the X-38 project may have infringed unless NASA makes a full and complete disclosure to me of that project. I also have no way of determining if NASA has (or has had) other projects that also infringe on my patent unless NASA makes a full and complete disclosure of those projects as well.

Therefore, in order to answer your question, I must request that NASA make a full and complete disclosure to me of the X-38 project as well as any other current or past projects that may infringe on my patent.

If this information requires a security clearance (I have none) I suggest you start the required security investigation immediately. If there is further information that you require in this regard feel free to contact me.

00024

(2)   The identification of all procurements known to the claimant or patent owner which involve the alleged infringing item or process, including the identity of the vendor or contractor and the Government procuring activity.

As I stated in my fax to you of June 7, 2003, I became aware that NASA was using synthetic vision in the X-38 project in the January 2003 issue of NASA Tech Briefs, page 40, **"Virtual Cockpit Window" for a Windowless Aerospacecraft.** The article is available at: http://www.nasatech.com/Briefs/Jan03/MSC23096.html

This led me to Rapid Imaging Software, Inc. and their press release (http://www.landform.com/pages/PressReleases.htm) which states:

"On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as 'the best seat in the house', the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight."

The RIS press release provided a link to an article in *Aviation Week & Space Technology:* http://www.aviationnow.com/avnow/news/channel_space.jsp?view=story&id=news/sx381211.xml

As a result of more searching I discovered a link to a Johnson Space Center SBIR Phase II award to Rapid Imaging Systems at   http://sbir.gsfc.nasa.gov/SBIR/successes/ss/9-058text.html .

It includes a particularly relevant paragraph:

The Advanced Flight Visualization Toolkit (VisualFlight™) project is developing a suite of <u>virtual reality immersive telepresence</u> software tools which combine the real-time flight simulation abilities with the data density of a Geographic Information System (GIS). This technology is used for virtual reality training of crews, analysis of flight test data, and as an on-board immersive situation display. It will also find application as a virtual cockpit, and in <u>teleoperation of remotely piloted vehicles.</u>

The emphasis on *virtual reality immersive telepresence* and *teleoperation of remotely piloted vehicles* is mine.

A search of the SBIR archive shows the following entries.

<u>For 2001 Phase I:</u>
Rapid Imaging Software, Inc.
████████████████████████   (b)(6)
████████████████████
Mike Abernathy████████
01 H6.02-8715 JSC
Integrated Video for Synthetic Vision Systems

For 2001 Phase II:
Rapid Imaging Software, Inc.

██████████████████
██████████████████ $(b)(6)$
Carolyn Galceran ██████████████
01-2-H6.02-8715 JSC

Since my sources of information are limited to those available to the public (magazines such as *Aviation Week & Space Technology* as well as whatever I can find on the Internet) I have no way of knowing if there are other procurements, vendors, contractors, and Government procuring activity related to Claim I-222.

I believe that NASA is in a better position to know what it is (or has been) working on than I am.

(3)   A detailed identification of the accused articles or processes, particularly where the article or process relates to a component or subcomponent of the item procured, an element by element comparison of the representative claims with the accused article or process. If available, this identification should include documentation and drawings to illustrate the accused article or process in suitable detail to enable verification of the infringement comparison.

I believe I have answered this in section (2) as much as I am able to without NASA's cooperation.

(4)   The names and addresses of all past and present licenses under the patent(s), and copies of all license agreements and releases involving the patent.

There are no past licenses for this patent, and as of this date there are no present licenses for this patent. Naturally, I reserve the right to license this patent in the future as I see fit.

(5)   A brief description of all litigation in which the patent(s) has been or is now involved, and the present status thereof.

There has been no past litigation involving this patent, and as of this date there is no present litigation regarding this patent.

(6)   *A list of all persons to whom notices of infringement have been sent, including all departments and agencies of the Government, and a statement of the ultimate disposition of each.*

As of this date NASA is the only agency or department of the Government against which I have filed a claim.

5/11/03 – sent email to *comments@hq.nasa.gov*

I believe that NASA may have infringed on one or more of my U.S. Patents.
How do I file a claim and whom do I contact?

5/11/03 – Received reply:

Date: Sun, 11 May 2003 17:48:46 -0400 (EDT)
From: "PAO Comments" <comments@bolg.public.hq.nasa.gov>
Message-ID: <200305112148.h4BLmkhJ011314@bolg.public.hq.nasa.gov>
To: <jm@jmargolin.com>
Subject: Thank you for your email.

Thank you for your message to the NASA Home Page. The Internet
Service Group will attempt to answer all e-mail regarding the site,
but cannot guarantee a response by a particular time. The group
will not be able to answer general inquiries regarding NASA,
which should instead be sent to public-inquiries@hq.nasa.gov

5/11/03 – Sent email to <public-inquiries@hq.nasa.gov>

I believe that NASA may have infringed on one or more of my U.S. Patents.
How do I file a claim and whom do I contact?

Jed Margolin

As far as I can tell I did not receive a response.   (b)(6)

5/12/03 – Sent email to ████████████████ (found on Web site)

I believe that NASA may have infringed on one or more of my U.S. Patents
How do I file a claim and whom do I contact?
(Or is my only recourse to sue in Federal Court?)

Jed Margolin

5/12/03 – Received reply:

Mr. Margolin,

Thank you for contacting NASA with your concerns. I have referred this matter to the Patent Counsel Office, and they will be contacting you to work with you on this issue.

Best wishes,
Jesse Midgett

5/12/03 – Given my experience with trying to contact Government officials via email (or mail, or fax) I hadn't waited for the reply from J. Midgett. I had found the web site for the LARC (NASA Langley) Patent Counsel Office, and called up. I was connected to Kurt Hammerle and we had a nice talk. I sent him an email the next day (May 13, 2003). (b)(6)

I received a phone call from Barry Gibbens ███████ who, apparently, was calling because of my email to to J.C.Midgett and hadn't seen the email I sent to K. Hammerle. (I explained to him what I had done.) We had a nice talk. He said he had already sent me a letter.

I received his letter and sent a reply on May 18, 2003 (USPS), adding to the email I had sent K. Hammerle.

Thursday, June 5, 2003 – Received message from B. Gibbens, asking me to call him because I should contact Alan Kennedy at NASA Headquarters ███████. (b)(6)

Friday, June 6, 2003 - I called B. Gibbens. Then I called A. Kennedy but he was out. (b)(6)

Saturday, June 7, 2003 – Sent a fax to A. Kennedy. The first number I tried ███████ only accepted 4 pages (out of 13). I tried a few times. Then I tried ███████ It turned out that 4341 was the correct number and that 2741 was another group. As a result, A. Kennedy initially only got 4 pages. (b)(6)

Monday, June 9, 2003 – Received message from A. Kennedy and called him back.

He had not gotten the fax so he went and found it. I learned the next day that he had only gotten 4 pages.

We had a "free and frank" discussion. I stressed that I wanted to resolve it in a friendly manner and that I preferred to have NASA buy the patent for the Government.

Tuesday, June 10, 2003 – Received a message from A. Kennedy and called him back.

He said that his Manager has turned down my request that NASA consider a license proffer and has decided to handle it as a Claim, and that the investigation would take 3-6 months.

However, NASA is not the only agency or department of the Government I have contacted.

7/5/1999 Email to █████████████ (b)(6)
Dr. Birckelbaw, Project Manager for the UCAV contract awarded to Boeing.

Introduced myself and asked if DARPA was interested in my patent.
Response: none

7/26/1999 USPS Mail to:
    Dr. Larry Birckelbaw
    Program Manager, Aerospace Systems
    DARPA Tactical Technology Office
    3701 North Fairfax Drive
    Arlington, VA 22203-1714

Introduced myself and asked if DARPA was interested in my patent. Enclosed copy of patent.
Response: none

Office of the Secretary of Defense (OSD)
    Mr. E.C. "Pete" Aldridge
    Under Secretary of Defense for Acquisition, Technology, and Logistics
    U.S. Department of Defense
    Contact Method: Email: webmaster@acq.osd.mil   May 3, 2002 and June 6, 2002
    Response: none

Army - AATD, Fort Eustice, VA.
    Col. Wado Carmona, Commander
    Applied Aviation and Training Directorate (AATD)
    Army Aviation and Missile Command
    Ft. Eustice, VA

    Contact Method:
    Email: Ms. Lauren L. Sebring   lsebring@aatd.eustis.army.mil   June 1, 2002
        757-878-4828, fax: 757-878-0008

    Phone Call Followup: She suggested I talk to Mr. Jack Tansey
        Mr. Jack Tansey, Business Development 757-878-4105   June 18, 2002
        Email Followup: jtansey@aatd.Eustis.army.mil   June 18, 2002

Air Force Research Laboratory (AFRL)
    Dr. Barbara Wilson
    Contact Method: email (Barbara.Wilson@wpafb.af.mil)   July 17, 2002
    Response - none

Air Force Research Laboratory (AFRL)
      Dr. R. Earl Good, Director,
      Directed Energy Directorate
      Air Force Research Laboratory
      Kirtland Air Force Base, NM 87117-5776
      Contact Method: Fax (505-846-0423)   July 23, 2002
      Response: none

Department of the Air Force
      Dr. James G. Roche
      Secretary of the Air Force
      Washington, DC

      Contact Method: Fax (703-695-8809)   July 28, 2002

      Response: Letter from
             Lt. General Charles F. Wald   August 13, 2002
             Deputy Chief of Staff, Air & Space Operations, USAF

(7)   A description of Government employment or military service, if any, by the inventor and/or patent owner.

I have never been employed by the U.S. Government (or any other government). Likewise, I have never been in military service (in the United States or elsewhere). In the interests of full disclosure, I worked for three summers (1967, 1968, 1969) at the RCA Astro-Electronics Division in Hightstown, NJ . (They had a summer job program for students.)

(8)   A list of all Government contracts under which the inventor, patent owner, or anyone in privity with him performed work relating to the patented subject matter.

None. I did this entirely on my own dime.

Air Force Research Laboratory (AFRL)
        Dr. R. Earl Good, Director,
        Directed Energy Directorate
        Air Force Research Laboratory
        Kirtland Air Force Base, NM 87117-5776
        Contact Method: Fax (505-846-0423)   July 23, 2002
        Response: none

Department of the Air Force
        Dr. James G. Roche
        Secretary of the Air Force
        Washington, DC

        Contact Method: Fax (703-695-8809)   July 28, 2002

        Response: Letter from   August 13, 2002
                Lt. General Charles F. Wald
                Deputy Chief of Staff, Air & Space Operations, USAF

*(7)   A description of Government employment or military service, if any, by the
        inventor and/or patent owner.*

I have never been employed by the U.S. Government (or any other government). Likewise, I have never been in military service (in the United States or elsewhere). In the interests of full disclosure, I worked for three summers (1967, 1968, 1969) at the RCA Astro-Electronics Division in Hightstown, NJ . (They had a summer job program for students.)

*(8)   A list of all Government contracts under which the inventor, patent owner, or
        anyone in privity with him performed work relating to the patented subject matter.*

None. I did this entirely on my own dime.

(9) *Evidence of title to the patent(s) alleged to be infringed or other right to make the claim.*

This appears to be a two-part question. Does the patent belong to Jed Margolin, and am I that Jed Margolin?

Part 1 - If you look at the front page of the '724 patent you will see that it was, indeed, issued to Jed Margolin, ▬▬▬▬▬▬▬▬▬ (b)(6)

If you contact the U.S. Patent and Trademark Office, Document Services Department (703-308-9726), you can order an Abstract of Title to verify that I own the patent. According to 37 CFR 1.12, assignment records are also open to public inspection at the United States Patent and Trademark Office.

Part 2 - If you look up Jed Margolin ▬▬▬▬▬▬▬ in a telephone directory you will find assigned to it the telephone number ▬▬▬▬ (b)(6)

When you called me on June 9 and June 10, that was the number you called.

Other than my affirming that I am, indeed, the Jed Margolin in question, I can only suggest that you contact my cousin Lenny (oops, I mean Dr. Len Margolin) who is employed by Los Alamos National Laboratory, and ask him if he has a cousin Jed who is an engineer and an inventor, and who possesses the Margolin gene for being very persistent. (Some say stubborn.) The last time I saw him was in Ann Arbor, Michigan, after he had just passed the orals for his doctorate. (He bought me a beer at a place on South University.)

(10) *A copy of the Patent Office file of the patent, if available, to claimant.*

I do not have a copy of the USPTO's patent file. What I have is my prosecution file which contains, among other things, privileged communications between my patent attorney and myself.

Besides, in our telephone conversation of June 10, you stated that one of the research centers (I believe it was LARC) had already ordered the file.

*(11)   Pertinent prior art known to claimant, not contained in the Patent Office file,
particularly publications and foreign art.*

I have found no relevant prior art.

However, there is an interesting article in the June 2, 2003 issue of *Aviation Week & Space Technology* on pages 48-51 entitled **GA Riding 'Highway-in-the-Sky'** which describes, among other things, the work of Dennis B. Berlinger, lead scientist for flight deck research at the FAA's Civil Aeromedical Institute (CAMI) regarding what is called **Performance-Controlled Systems**. In the Specification of my '724 patent I call it **First Order RPV Flight Control Mode**. In Claim 18:

> 18. The station of claim 13, wherein said set of remote flight controls are configured to allow inputting absolute pitch and roll angles instead of pitch and roll rates.

An Internet search turned up Mr. Beringer's report **Applying Performance-Controlled Systems, Fuzzy Logic, and Fly-By-Wire Controls to General Aviation** as DOT/FAA/AM-02/7.

I am pleased that Mr. Beringer's May 2002 study confirms the value of Performance-Controlled Systems in piloted aircraft and I believe that teaching it in my '724 patent (filed January 19, 1999) gave an additional novel and useful aspect to my invention.

(The article also describes the Synthetic Vision system used in the FAA's Capstone program.)

If you have any further questions, please contact me.

Sincerely yours,

Jed Margolin

Jed Margolin

Enclosed: Response from General Wald
AWST article
Beringer Report
U.S. Patent 5,904,724

Reference 1 (1 Page)

National Aeronautics and
Space Administration

Langley Research Center (b)(6)

NASA

May 14, 2003

Reply to Attn of: 212

Jed Margolin
(b)(6)

Subject: Infringement Inquiry

Dear Mr. Margolin,

I received notice of your belief that NASA may have infringed one or more of your U.S. patents. In order to address your concerns, we need to receive some more detailed information. Please provide the titles and patent numbers of any patents you feel NASA may have infringed. Please also provide a description of any actions by NASA leading to your belief of possible infringement. Finally, please specify in detail how those actions constitute infringement of your patent(s). This information will allow us to evaluate your assertion and respond and/or react appropriately. Thanks for contacting us. I look forward to hearing from you soon, and discussing your concerns further.

Cordially,

Barry V. Gibbens
Patent Attorney
Technology Commercialization
  Program Office

{00009174.1}

Jed Margolin   **May 18, 2003**

Mr. Barry V. Gibbens
National Aeronautics and Space Administration
Langley Research Center
100 NASA Road
Hampton, VA 23681-2199

Attn: 212

Dear Mr. Gibbens,

This is in response to your letter dated May 14, 2003.

As we discussed in our telephone conversation on May 16, the information you have requested was supplied in my email to Mr. Kurt Hammerle on May 12, 2003.

After I emailed my inquiry to Mr. Jesse Midgett on May 12, I discovered the web page for the Patent Counsel Office and contacted Mr. Hammerle by telephone.

I apologize for any confusion this may have created.

As a result of more searching I have discovered a link to a Johnson Space Center SBIR Phase II award to Rapid Imaging Software at   http://sbir.gsfc.nasa.gov/SBIR/successes/ss/9-058text.html .

It includes a particularly relevant paragraph:

> *The Advanced Flight Visualization Toolkit (VisualFlight™) project is developing a suite of* <u>*virtual reality immersive telepresence*</u> *software tools which combine the real-time flight simulation abilities with the data density of a Geographic Information System (GIS). This technology is used for virtual reality training of crews, analysis of flight test data, and as an on-board immersive situation display. It will also find application as a virtual cockpit, and in* <u>*teleoperation of remotely piloted vehicles.*</u>

(The emphasis on teleoperation of remotely piloted vehicles is mine.)

A search of the SBIR archive shows the following entries.

For 2001 Phase I:

Rapid Imaging Software, Inc.
                                      (b)(6)

Mike Abernathy
01 H6.02-8715 JSC
Integrated Video for Synthetic Vision Systems

For 2001 Phase II:

Rapid Imaging Software, Inc.

████████████.
████████████ $(b)(6)$
Carolyn Galceran (████████,
01-2-H6.02-8715 JSC
Integrated Video for Synthetic Vision Systems

If there is any additional information regarding my patents that you would find helpful please let me know.

Sincerely yours,

Jed Margolin

Jed Margolin

NASA SBIR SUCCESSES

Johnson Space Center
1998 Phase II

LandForm VisualFlight™

Rapid Imaging Software, Inc.

Alberqueque, NM

Optional Powerpoint file

INNOVATION

LandForm VisualFlight™ is the power of a geographic information system (GIS) and the speed of a flight simulator, accessible from any Windows application.

ACCOMPLISHMENTS

- The Advanced Flight Visualization Toolkit (VisualFlight™) project is developing a suite of virtual reality immersive telepresence software tools which combine the real-time flight simulation abilities with the data density of a Geographic Information System (GIS). This technology is used for virtual reality training of crews, analysis of flight test data, and as an on-board immersive situation display. It will also find application as a virtual cockpit, and in teleoperation of remotely piloted vehicles.

- AFVT will enhance the ability of analysts and operators to interact with large amounts of multidimensional data using the most natural paradigm available: 3D immersion. This operator/data interaction technology will be an advancement comparable to the invention of the Heads-Up Display (HUD). AFVT will move the HUD into the third dimension.

- A simplified user interface, it will fuse real-time 3D displays of terrain with digital maps, satellite data, vehicles, flight paths, and waypoints. This unique and innovative approach will build upon recent software technology research and development from Rapid Imaging Software. VisualFlight™ permits users to construct and deploy their own immersive multidimensional display applications on Windows-based computer platforms.

COMMERCIALIZATION

- VisualFlight™ is sold as a development kit starting with 5 run-time licenses. Users who wish to distribute more applications

GOVERNMENT/SCIENCE APPLICATIONS

- The firm's VisualFlight™ System was used to fly the X-38 on it's latest test flight. The flight vehicle was piloted by astronaut (Ken Ham) using LandForm VisualFlight

using LandForm VisualFlight™ technology can purchase additional run-time licenses as needed.

- VisualFlight™ 1.0 has been available to qualified users for several months now, and the response is excellent. VisualFlight™ has been deployed to display live real-time flight data broadcast over a network. Please visit this page for the latest VisualFlight™ developments.
- **LandForm V/O Video Overlay** plug-in for LandForm C3 or Flight Vision is available for the Matrox Corona board only. The price is $4995 for a # single users license. Site license is available for $6995.

system as his digital cockpit window.

For more information about this firm, please send e-mail to: company representative

Return to NASA SBIR Success Listings   Curator: SBIR Support

Synthetic Vision Technology for Unmanned Aerial Systems: The Real Story

By Jed Margolin
January 7, 2009

Contents

Introduction

This is in response to the article **Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward** by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun which appeared in the December 2008 issue of AUVSI's Unmanned Systems (page 27). *[Ref. 1]*

The AUVSI Authors have used the term "synthetic vision" so loosely that many readers will believe it was invented long before it actually was. This is an important issue. Aerospace is a field where precision and accuracy is critical. There are also patent rights involved. In the interests of full disclosure I am the listed inventor on several patents relating to synthetic vision and there is a patent infringement disagreement between the owner of the patents (Optima Technology Group) and the company that one of the AUVSI Authors is affiliated with (Rapid Imaging Software).

What Is Synthetic Vision?

The term "Synthetic Vision" originally meant anything that you put up on a video display.

For example, there is U.S. Patent 5,593,114 **Synthetic Vision Automatic Landing System** issued January 14, 1997 to Ruhl (Assignee McDonnell Douglas Corporation). *[Ref. 2]*

From Column 2, lines 16 - 27:

> The instant invention is an Enhanced or Synthetic Vision (also called Autonomous) Landing System (E/SV). This system allows the pilot to view the approach scene with the use of a forward looking radar or equivalent sensor which provides the means of identifying the runways and the airport and land the aircraft using the automatic landing systems on virtually all types of aircraft. A pilot effectively turns the flight task during zero visibility or other low visibility weather conditions into a synthetic "see to land" approach because the image from the forward looking sensor provides sufficient detail to turn any instrument landing into what appears to be a visual landing.

In this patent Enhanced or Synthetic Vision is a display of the data from a forward looking radar or equivalent sensor.

This was also the FAA's definition at the time, in their **Synthetic Vision Technology Demonstration, Volume 1 of 4, Executive Summary** *[Ref 3]*. From PDF page 10:

1.1 BACKGROUND

> In 1988 the Federal Aviation Administration (FAA), in cooperation with industry, the United States Air Force (USAF), the Navy, and several other government organizations initiated an effort to demonstrate the capabilities of existing technologies to provide an image of the runway and surrounding environment for pilots operating aircraft in low visibility conditions. This effort was named the Synthetic Vision Technology Demonstration (SVTD) program. Its goal was to document and demonstrate aircraft sensor and system performance achieved with pilots using millimeter wave (MMW) radar sensors, a forward-looking infrared (FLIR) sensor, and a head-up display (HUD).

And from PDF pages 11,12:

1.2. OBJECTIVE

The objective of the Synthetic Vision Technology Demonstration program was to develop, demonstrate, and document the performance of a low-visibility, visual-imaging aircraft landing system. The experimental Synthetic Vision System components included on-board imaging sensor systems using millimeter-wave and infrared technology to penetrate fog, and both head-up (HUD) and head-down (HDD) displays. The displays presented the processed raster image of the forward scene, combined with suitable avionics-based stroke symbology for the pilot's use during a manually flown approach and landing. The experimental system, sometimes referred to as a functional prototype system, included all the functions (in prototype form only) required to accomplish precision, non-precision, and non-instrument approaches and landings in low visibility weather conditions.

In the AUVSI Authors' own article they equate "pictorial format avionics" with "synthetic vision." [Paragraph 10]:

Pictorial format avionics (i.e., synthetic vision) formed a key ingredient of the Air Force Super Cockpit concept.

Boeing's report **Multi-Crew Pictorial Format Display Evaluation** *[Ref. 4]* describes what Pictorial Format means (PDF Page 17):

The Multi-Crew Pictorial format Display Evaluation Program is the third in a series of contracted efforts, sponsored primarily by the Air Force Flight Dynamics Laboratory, Crew Systems Development Branch, (AFWAL/FIGR). In the first of these efforts, conceptual displays were developed for six primary fighter crew station functions: primary flight, tactical situation, stores management, systems status, engine status, and emergency procedures (Jauer and Quinn, 1982).

In the second contract, Pictorial Format Display Evaluation (PFDE), the Boeing Military Airplane Company continued the development beyond the paper formats of the earlier program and implemented the results in a piloted simulation. Two simulation studies were conducted to evaluate the usability and acceptability of pictorial format displays for single-seat fighter aircraft; to determine whether usability and acceptability were affected by display mode -- color or monochrome; and to recommend format changes based on the simulations. In the first of the two PFDE studies, pictorial formats were implemented and evaluated for flight, tactical situation, system status, engine status, stores management, and emergency status displays. The second PFDE study concentrated on the depiction of threat data. The number of threats and the amount and type of threat information were increased. Both PFDE studies were reported in Way, Hornsby, Gilmour, Edwards and Hobbs, 1984.

Pictorial Format Avionics is pictures. That explains why it is called **Pictorial** Format Avionics.

Why can't we use the term "Synthetic Vision" to mean anything we want it to mean?

1. It is sloppy.

2. The FAA has a definition for "Synthetic Vision" and if you want an FAA type certificate for your Synthetic Vision product you have to use their definition.

00557

{Ref. 5 – FAA current definition of synthetic vision}

> Synthetic vision means a computer-generated image of the external scene topography from the perspective of the flight deck that is derived from aircraft attitude, high-precision navigation solution, and <u>database of terrain</u>, obstacles and relevant cultural features.

{Emphasis added}

{Ref. 6 – FAA Synthetic Vision is based on a Digital Elevation Database}

> "Everyone gets their data from the same original source."

> "If accuracy of data base must be validated then SV is unapproveable."

> "Current resolution tends to round-up <u>the elevation data</u> so that small errors are not as significant and on the conservative side."

{Emphasis added}

Therefore, Synthetic Vision means a computer-generated image of the external scene topography from the perspective of the flight deck that is derived from aircraft attitude, high-precision navigation solution, and digital terrain elevation database, obstacles and relevant cultural features.

Implicit in this is that in order for the external scene topography to be viewed from the perspective of the flight deck it has to be a 3D projected view and that the digital terrain elevation database must represent real terrestrial terrain, as opposed to terrain that is simply made up.

Digital Terrain Elevation Database

The **Digital Terrain Elevation Database** is also called the **Digital Elevation Database** or **Digital Elevation Model**. From *Ref. 7*:

> The USGS Digital Elevation Model (DEM) data files are digital representations of cartographic information in a raster form. DEMs consist of a sampled array of elevations for a number of ground positions at regularly spaced intervals. These digital cartographic/geographic data files are produced by the U.S. Geological Survey (USGS) as part of the National Mapping Program and are sold in 7.5-minute, 15-minute, 2-arc-second (also known as 30-minute), and 1-degree units. The 7.5- and 15-minute DEMs are included in the large scale category while 2-arc-second DEMs fall within the intermediate scale category and 1-degree DEMs fall within the small scale category - (Source: USGS)

The Digital Elevation Model was substantially improved by STS-99 when Endeavour's international crew of seven spent 11 days in orbit during February 2000 mapping the Earth's surface with radar instruments. *{Ref. 8}*

Displaying the Digital Elevation Database

Now that we have a Digital Elevation Database consisting of a sampled array of elevations for a number of ground positions at regularly spaced intervals, what do we do with it? The database is just elevation points.

If you display only points there is no way to remove "hidden points" because there are no surfaces to test them against. (Things can only be hidden behind surfaces.) The result is a jumble which looks like this (the only useful features are the highest peaks):

This following picture shows the same scene rendered in polygons. (The polygons are crude because I had only a few colors to work with and there is no clipping, only polygon sorting):

After you have used the digital elevation points to produce polygons you can shade and blend the polygons so that the underlying polygons may no longer be obvious. Honeywell did an excellent job in their IPFD (Instrument Primary Flight Display) *[Ref. 9]*:

NASA HiMAT

The AUVSI Authors have gone to considerable lengths to persuade readers that NASA's HiMAT project was Synthetic Vision [Paragraphs 11 – 14]. It wasn't.

HiMAT - Summary

<u>Sarrafian (*Ref. 11*)</u>

1. "The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach."

2. During the operational phase of the HiMAT program, a simulator was used to adjust the control laws for the primary control system. The display presented to the pilot of this simulated system was a display of an instrument landing system (ILS).

3. <u>Separately</u>, a study was undertaken to compare evaluations of pilots using a <u>simulated visual display of the runway scene</u> and a <u>simulated ILS display</u> with the results of actual flight tests, using the HiMAT aircraft as a representative remotely piloted research vehicle.

There is no mention of a terrain database or any suggestion that the simulated visual display of the runway scene was ever used to control a real aircraft. It was never anything other than a simulation.

<u>From Evans and Schilling (Ref. 13)</u>:

Visual Landing Aid

<u>Actual.</u> - Cues to the pilot during landing included the cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

<u>Simulation model.</u> - For most of the program, the landing cues for the pilot in a HiMAT simulation included only the instruments, mapboards, and the ILS/glideslope error indicators. Although these are all valid cues, they could not achieve the same effect as the television transmission used in actual flight. During flight, as soon as the pilot can identify the runway, his scan focuses more on the television picture and less on the cockpit instruments. To help alleviate this lack of fidelity in the simulation, a display of the runways on the dry lakebed was developed on a recently purchased Evans and Sutherland Graphics System.

HiMAT Details

From NASA's description of the HiMAT project *{Ref. 10}*:

> **Highly Maneuverable Aircraft Technology**
>
> From mid-1979 to January 1983, two remotely piloted, experimental Highly Maneuverable Aircraft Technology (HiMAT) vehicles were used at the NASA Dryden Flight Research Center at Edwards, Calif., to develop high-performance fighter technologies that would be applied to later aircraft. Each aircraft was approximately half the size of an F-16 and had nearly twice the fighter's turning capability.

and, later:

> The small aircraft were launched from NASA's B-52 carrier plane at an altitude of approximately 45,000 feet. Each HiMAT plane had a digital on-board computer system and was flown remotely by a NASA research pilot from a ground station with the aid of a television camera mounted in the cockpit. There was also a TF-104G chase aircraft with backup controls if the remote pilot lost ground control.

NASA's article says it was flown remotely by a pilot using a television camera in the aircraft. It does not say it was flown using what is now known as synthetic vision. (As previously explained, the definition of the term "synthetic vision" has changed over the years.)

It does say:

> Dryden engineers and pilots tested the control laws for the system, developed by the contractor, in a simulation facility and then in flight, adjusting them to make the system work as intended.

and that is where the AUVSI Authors have gone astray, whether deliberately or through poor scholarship.

The AUVSI Authors cite the report by Shahan Sarrafian,**"Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display."** There are two Sarrafian reports with that title, one dated May 1984; the other dated August 1984. See *Ref. 11* which contains links to the reports as well as to mirrored copies. The August 1984 report has been converted to text to make it easy to search and to quote from.

The title of the Sarrafian report gives an accurate description of his project, **"Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display."**

It was a simulation.

Here is the Introduction from the report. It's a little long but it describes the heart of the matter. I have underlined the parts that are especially relevant.

<div align="center">

Introduction

</div>

The remotely piloted research vehicle (RPRV) is a tool that can be used for exploring unproven and advanced technologies without risking the life of a pilot. The flight testing of RPRVs(1) allows programs to be conducted at a low cost, in quick response to demand, or when hazardous testing is required to assure the safety of manned vehicles. Yet this type of testing must be performed by the most versatile

system available - the pilot. The pilot has the same responsibilities and tasks as if he were onboard the aircraft; this includes guiding the vehicle to a safe landing. The only difference is that he must accomplish this final task from a ground-based cockpit.

The highly maneuverable aircraft technology (HiMAT) aircraft (Fig. 1) is a remotely piloted research vehicle that has completed flight tests to demonstrate advanced fighter technologies at NASA Ames Research Center's Dryden Flight Research Facility. The HiMAT vehicle is a 0.44-scale version of an envisioned small, single-seat fighter airplane. The mission profile of HiMAT (Fig. 2) included a launch from a B-52 aircraft and the acquisition of flight test data. The vehicle was then flown by a NASA test pilot in a fixed ground-based cockpit to a horizontal landing on the Edwards dry lakebed. The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach.

During the operational phase of the HiMAT program, the lateral-stick gearing gain used in the aircraft approach was altered from a variable gain schedule (derived from simulation) to a constant gain schedule. The schedules were changed in response to pilot complaints about oversensitivity in the lateral stick that required high pilot compensation. Before the modified gain schedule was implemented into the primary control system (PCS), it was evaluated in the HiMAT simulator using an instrument landing system (ILS) display; the schedule was found to be satisfactory. Postflight comments from HiMAT pilots indicated that the handling qualities during landing approach were significantly improved as a result of the modified gain schedule.

In a separate development, a visual display that was used for engineering purposes was implemented into the simulator during the latter portion of the flight test program when simulation was no longer required to support the remaining flights. While the addition of a visual display is known to significantly improve the fidelity of a simulation system, the need for such a system in RPRV simulation at Ames Dryden was felt to be reduced since pilots had an opportunity to conduct proficiency flights with an RPRV Piper Comanche PA-30 aircraft. Nevertheless, when a visual display became available in the simulation laboratory, a decision was made to determine the effectiveness of this type of visual display in the simulation of visual RPRV flight. The RPRV evaluation described in this paper was designed to focus on the utility of a visual display of this type while studying the influence of changes in lateral-stick gearing gains of remotely piloted research vehicle handling qualities during simulated approaches and landings. This study was undertaken to compare evaluations of pilots using a simulated visual display of the runway scene and a simulated ILS display with the results of actual flight tests, using the HiMAT aircraft as a representative remotely piloted research vehicle.

What this says is:

1. "The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach."

2. During the operational phase of the HiMAT program, a simulator was used to adjust the control laws for the primary control system. The display presented to the pilot of this simulated system was a display of an instrument landing system (ILS).

3. Separately, a study was undertaken to compare evaluations of pilots using a simulated visual display of the runway scene and a simulated ILS display with the results of actual flight tests, using the HiMAT aircraft as a representative remotely piloted research vehicle.

There is no mention of a terrain database or any suggestion that the simulated visual display of the runway scene was ever used to control a real aircraft. It was never anything other than a simulation.

Sarrafian does not show a picture of the ILS display. He probably assumed that anyone reading the report in 1984 would know what one looks like.

The following is a modern picture and an explanation of an ILS display from NASA *[Ref. 12]*. Note that the sky above the horizon line is blue; the ground below the horizon line is brown. There is no depiction of terrain. This looks a great deal like what is now known as a Primary Flight Display.

Instrument Landing System (ILS)

An aircraft on an instrument landing approach has a cockpit with computerized instrument landing equipment that receives and interprets signals being from strategically placed stations on the ground near the runway. This system includes a "Localizer" beam that uses the VOR indicator with only one radial aligned with the runway. The Localizer beam's width is from 3° to 6°. It also uses a second beam called a "glide slope" beam that gives vertical information to the pilot. The glide slope is usually 3° wide with a height of 1.4°. A horizontal needle on the VOR/ILS head indicates the aircraft's vertical position. Three marker beacons (outer, middle and inner) are located in front of the landing runway and indicate their distances from the runway threshold. The Outer Marker (OM) is 4 to 7 miles from the runway. The Middle Marker (MM) is located about 3,000 feet from the landing threshold, and the Inner Marker (IM) is located between the middle marker and the runway threshold where the landing aircraft would be 100 feet above the runway.

The VOR indicator for an ILS system uses a horizontal needle in addition to the vertical needle. When the appropriate ILS frequency is entered into the navigation radio, the horizontal needle indicates where the aircraft is in relation to the glide slope. If the needle is above the center mark on the dial, the aircraft is below the glide slope. If the needle is below the center mark on the dial, the aircraft is above the glide slope.

The following is a picture of the image Sarrafian produced in his simulator (*Figure 9 - Simulated landing approach conditions on glideslope*):

The display was created with an Evans and Sutherland Picture System *{Ref. 16}* using a calligraphic monitor. The term *calligraphic* means that the system only drew lines and dots. This type of system is also called *Random Scan* because the electron beam in the CRT can be moved anywhere on the screen, as opposed to a Raster Scan system, which draws a raster. Atari's term for *Random Scan* was *XY* or *Vector* and was used in several games in the late 1970s and early 1980s such as Asteroids, BattleZone, and Star Wars.

The solid areas are filled-in by drawing lots of lines.

The lines above the horizon are presumably meant to indicate the sky. The grid lines are presumably meant to indicate the ground. There is no suggestion that the grid lines are produced from a digital elevation database. There would be no reason to use a digital elevation database because the system was used only to simulate landings. (Indeed, the name of the study is "Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display.")

Another HiMAT report is **THE ROLE OF SIMULATION IN THE DEVELOPMENT AND FLIGHT TEST OF THE HIMAT VEHICLE by** M. B. Evans and L. J. Schilling *[Ref. 13]*.

From Evans and Schilling:

<p style="text-align:center">Visual Landing Aid</p>

Actual. - Cues to the pilot during landing included the cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

Simulation model. - For most of the program, the landing cues for the pilot in a HiMAT simulation included only the instruments, mapboards, and the ILS/glideslope error indicators. Although these are all valid cues, they could not achieve the same effect as the television transmission used in actual flight. During flight, as soon as the pilot can identify the runway, his scan focuses more on the television picture and less on the cockpit instruments. To help alleviate this lack of fidelity in the simulation, a display of the runways on the dry lakebed was developed on a recently purchased Evans and Sutherland Graphics System.

HiMAT was actually flown using cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

It was not flown using synthetic vision.

The AUVSI Authors have reproduced a picture in their article with the caption, "The HiMAT RPV remote cockpit showing synthetic vision display. Photo courtesy of NASA."

This picture is identical to the picture in Sarrafian Figure 5 {Ref. 11}, August 1984, PDF page 10} but the Sarrafian picture has a different caption. It says, " HiMAT simulation cockpit."

The HiMAT RPV remote cockpit showing synthetic vision display. Photo courtesy of NASA.

Fig. 5 HiMAT simulation cockpit.

The monitor shows a picture of the kind shown in Sarrafian Figure 8 or Figure 9 (along with a considerable amount of what appears to be reflected glare). The picture was produced by an Evans and Sutherland Picture System which requires a calligraphic monitor.

Here's the thing. "The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach."

In order to display the video from the camera aboard the aircraft, the Ground Cockpit that controlled the aircraft had to have a raster-scan monitor.

Raster-scan monitors and Calligraphic monitors are incompatible.

The picture shows the Simulation Cockpit, and the Simulation Cockpit could not be used to control the aircraft.

Why did the AUVSI Authors change the caption?

Visual-Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles, Reed, 1977

In paragraph 9 the AUVSI Authors state:

> Also in 1979, the Air Force published research identifying human factors problems that would have to be overcome in RPV cockpit design ("Visual- Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles" by Reed in 1977). NASA would use this in the design of the HiMAT RPV 3D visual system in 1984.

Ref. 14 provides the link to the Reed report.

This is what the Reed report was about:

1. From page 5 (PDF page 8):

An operator is asked to maneuver a remotely piloted vehicle (RPV) from an airborne control station (a mother ship). This station is equipped with a television monitor, control stick, and other controls and displays necessary to maneuver the RPV through a specified course. The RPV, containing a television camera mounted in its nose, relays an image of the terrain to be displayed on the television monitor in the control station. Thus, the visual scene displayed to the operator represents the scene viewed by the camera. The task of the operator is to use the controls and displays to "fly" the RPV in much the same way he would fly a conventional aircraft.

The scenario is complicated by several factors. First, the visual inputs to the operator from the RPV are independent of the motion inputs from the control station. Thus, the operator will experience motion cues that are uncorrelated with the visual inputs received from the RPV. Second, while traditional pilot training programs operate on the philosophy that proprioceptive cues provided by the motion of the aircraft should be disregarded, research has shown that these cues are compelling, not easily ignored, and may improve performance when used in training simulators (see, for example, Borlace, 1967; Cohen, 1970; Douvillier, Turner, McLean, & Heinle, 1960; Fedderson, 1961; Huddleston & Rolfe, 1971; Rathert, Creer, & Douvillier, 1959; Ruocco, Vitale, & Benfari, 1965). The task simulated in the experiment presented here, however, required that the RPV operator disregard sensations of motion in order to maintain adequate performance. Under conditions of visual -proprioceptive conflict (as when the mother ship and/or the RPV are in turbulence) the stereotypic responses of pilots to correct angular accelerations will be inappropriate.

2. From page 7 (PDF page 10):

Visual system. The visual system consisted of a three-dimensional terrain model (a modified SMK-23 Visual Simulator, The Singer Company), television camera and optical probe, and three monochromatic television monitors. The terrain model provided "real-world ground cues for visual tracking over the surface. The real-world to terrain model scale was 3,000:1 and represented a six by twelve-mile (9.65 by 19.3 km) area. The model was mounted on an endless belt that was servo-driven to represent the continuous changes in scene as the simulated RPV traveled along north-south directions. A television camera viewed the terrain model through an optical probe that contained a servoed mechanical assembly to permit the introductions of heading, roll, and pitch. Both the camera and probe were mounted on a servo-driven carriage system that moved across the terrain model to simulate movement of the RPV along east-west directions and in and out to simulate altitude changes.

The SMK-23 was also used in The Lunar Roving Vehicle (LRV) simulator *[Ref. 15]*. This shows what an SMK-23 looks like.

LRV SIMULATION

The SMK-23 used a television camera with an optical probe to fly over the terrain model contained on a servo-driven endless belt.

If Reed had had *synthetic vision* why would he have used the SMK-23 mechanical contraption?

The only link between Reed and HiMAT is that the HiMAT aircraft could be landed by either a ground-based pilot or an airborne controller (the backseat chase pilot in the TF-104G aircraft). {*Ref 13* – Evans & Schilling, PDF page 9}

> Actual.- The backup control system (BCS) is the second of the two independent flight control systems required for the Hi MAT program. The BCS control law is resident in one of the two onboard digital computers. The BCS is a full-authority, three-axis, multirate digital controller with stability augmentation functions and mode command functions (ref. 4). Each of seven modes is semiautomatic with the pilot providing direction by way of discrete command inputs. The BCS commands elevons for pitch and roll control and rudders for yaw control, and has an autothrottle for speed modulation.

The BCS was designed to provide well-controlled dynamics throughout the flight envelope, to have the ability to recover from extreme attitudes, and to bring the vehicle to a selected site and effect a successful landing by either a ground-based pilot or an airborne controller (the backseat chase pilot in the TF-104G aircraft). It was designed to provide these features for an unstable vehicle configuration of no more than 10-percent aft mean aerodynamic chord center-of-gravity location. The original HiMAT BCS was developed by Teledyne Ryan Aeronautical for the onboard microprocessor computer, and was programmed entirely in Intel 8080 assembly language.

While HiMAT might have used the results of the Reed report to select the airborne controller (the backseat chase pilot in the TF-104G aircraft) Reed did not use synthetic vision and neither did HiMAT.

Simulators

The AUVSI Authors describe several flight simulators, such as the RC AeroChopper by Ambrosia Microcomputer Products [Paragraphs 15 and 16] and Bruce Artwick's "Flight Simulator" for the Apple II, which ultimately became Microsoft Flight Simulator. [Paragraph 5]

RC AeroChopper was developed by David R. Stern at Ambrosia Microcomputer Products. The following is from an email correspondence with Mr. Stern:

Question 1: Did AeroChopper use a 3D terrain database?

> Mr. Stern: I guess it did, although the ground was a plane with 3D objects (and a 2D runway) scattered around (trees, pylon, towers with crossbar to fly under).

Question 2: If so, did it represent real terrestrial terrain?

> Mr. Stern: No.

Question 3: Did AeroChopper do real 3D?

> Mr. Stern: Yes. All the objects including the aircraft were described by a list of points, a list of point pairs for lines and a list of which points were in each polygon, each point had an x,y and z component. The original version was started in 1984, shown at the first R/C show (I think in Storm Lake Iowa) in the summer of 1986, had only vector graphics. About 1990 I changed to filled polygons. The aircraft was rotated (pitch, yaw and roll) slightly each frame with respect to the fixed coordinate system. Then the aircraft and all background objects were rotated and scaled depending on the relative position of the "camera".
>
> The view on the screen was initially from a fixed point about eye level for a standing R/C pilot. The "camera" rotated to keep the aircraft on the screen. In the late 80s, I added two different viewpoint options ("camera" flying near the aircraft) . One mode was just behind the aircraft, looking in the direction the aircraft was pointed. The second camera mode followed the aircraft to keep it from getting too far away but slowed and stopped as the aircraft got closer. You can often see the ground objects from the air in these modes.
>
> I developed the first version on the Atari 520 ST computer in 68000 assembly language. Then I developed an Amiga version and then a Macintosh version. In about 1991, I developed an 80286 version for a DOS machine. (The latest version requires a Windows 98 or older machine with an RS232 port and runs under DOS)

RC AeroChopper was a significant achievement for the home computers available at the time and was a highly regarded simulator {_Ref. 17_} but:

> 1. It did not use a digital elevation database; "... the ground was a plane with 3D objects (and a 2D runway) scattered around (trees, pylon, towers with crossbar to fly under)," and thus, did not represent real terrestrial terrain.

2. It did not provide a computer-generated image of the <u>external scene topography from the</u> <u>perspective of the flight deck</u> that is <u>derived from aircraft attitude, high-precision navigation solution,</u> <u>and database of terrain</u>, obstacles and relevant cultural features.

It was not synthetic vision. It was a simulator.

Now, let's discuss Microsoft Flight Simulator *{Ref. 18}*:

Flight Simulator 5.1 was released in 1995. Microsoft Flight Simulator did not start using 3D terrain until Flight Simulator 2000 Pro, released in late 1999.

From *Ref. 19*:

GRAPHICS

We now have another complete globe to fly around. With the new mesh style scenery we have real elevation points that make the surrounding terrain rise and fall like the real earth. We have no more flat areas that just pop up into place at the last minute during a landing approach!

Even then, it is not clear if the terrain database represents real terrain or is made up.

The article mentions the new GPS feature:

737 Panel

The 737-400 panel is very nicely done. Simple, yet effective. This is where FS2000 is not much different than FS98. However, the overall clarity, coloring, detailing and some new systems make it much better. We now have nice popups for the throttle quadrant, radio stack, compass and best of all the new GPS.

The GPS is part of the simulated 737 control panel. There is no suggestion that a physical GPS unit can be connected to the program.

A simulator is not synthetic vision. A simulator might do a good job simulating synthetic vision. It might even use a Digital Terrain Elevation Database representing real terrestrial terrain, but that does not make it synthetic vision. It is a simulator. If it does not control a physical aircraft it is not synthetic vision.

When Did NASA Start Working on Synthetic Vision?

From *Ref 20*:

NEWS RELEASE

May 28, 1999

Synthetic Vision Could Help General Aviation Pilots Steer Clear of Fatalities

Hampton, Virginia -- Research Triangle Institute and six companies are teaming up to develop revolutionary new general aviation cockpit displays to give pilots clear views of their surroundings in bad weather and darkness.

The RTI Team includes Flight International, Inc., Newport News, Virginia. (a GA aircraft user) and Archangel Systems, Inc., Auburn, Alabama, who are committed to early commercialization and will make significant cost share contributions. The starting point for the new system is Archangel's TSO'd and STC'd Cockpit Display System.

RTI also has teamed with Seagull Technology, Inc., Los Gatos, California (a GPS and attitude/heading reference system technology firm), Crew Systems, Inc., San Marcos, Texas, (a designer of low-cost head up displays), and Dubbs & Severino, Inc., Irvine, California (an award-winning terrain database design company). In addition, FLIR Systems, Inc., Portland, Oregon (an infrared instrument manufacturer) has agreed to evaluate the costs and benefits of existing weather penetrating sensor technology.

Limited visibility is the greatest factor in most fatal aircraft accidents, according to the Aviation Safety Program at NASA's Langley Research Center in Hampton, VA. The RTI team is among six selected by NASA to develop different applications of Synthetic Vision.

The RTI team will design, develop, and certify a Synthetic Vision system for general aviation aircraft. The purpose is to reduce or eliminate controlled flight into terrain caused by visibility-induced human error.

Synthetic Vision is a display system that will offer pilots an electronic picture of what's outside their windows, no matter the weather or time of day. The system combines Global Positioning Satellite signals with terrain databases and graphical displays to draw three-dimensional moving scenes that will show pilots exactly what's outside.

The NASA Aviation Safety Program envisions a system that incorporates multiple sources of data into cockpit displays. The displays would show hazardous terrain, air traffic, landing and approach patterns, runway surfaces and other obstacles that could affect an aircraft's flight.

The NASA Aviation Safety Program is a partnership with the FAA, aircraft manufacturers, airlines and the Department of Defense. This partnership supports the national goal announced by President Clinton to reduce the fatal aircraft accident rate by 80 percent in 10 years and by 90 percent over 25 years.

Research Triangle Institute is an independent, not-for-profit organization that conducts R&D and provides technical services to industry and government. With a staff of more than 1,600 people, RTI is active in aerospace and many other fields of applied technology. RTI was created in 1958 as the centerpiece of North Carolina's Research Triangle Park, where its headquarters are located. RTI's Aerospace Technology Center in Hampton, Virginia, will carry out the Synthetic Vision project.

In a separate press release dated May 13, 1999 NASA announced {from *Ref. 21*}:

Industry teams submitted 27 proposals in four categories: commercial transports and business jets, general aviation aircraft, database development and enabling technologies. NASA and researchers from the Federal Aviation Administration and Department of Defense evaluated the proposals' technical merit, cost and feasibility.

NASA has committed $5.2 million that will be matched by $5.5 million in industry funds to advance Synthetic Vision projects over the next 18 months. More money is expected to be designated later to accelerate commercialization and make some systems available within four to six years.

Among the team leaders selected for the first phase of the program are: Rockwell Collins, Inc., Cedar Rapids, IA; AvroTec, Inc., Portland, OR; Research Triangle Institute, Research Triangle Park, NC; Jeppesen-Sanderson, Inc., Englewood, CO; the Avionics Engineering Center of Ohio University, Athens, OH; and Rannoch Corporation, Alexandria, VA.

Rockwell Collins, Inc. will receive funds to develop synthetic vision for airliners and business jets. The AvroTec, Inc. and Research Triangle Institute groups will use their awards to create technologies for a general-aviation synthetic vision system. A team led by Jeppesen-Sanderson, Inc. will receive funds to develop terrain database requirements and system approaches. The Avionics Engineering Center of Ohio University and Rannoch Corporation will use their awards to design specific component technologies for Synthetic Vision.

When did NASA start working on Synthetic Vision?

The answer is: 1999.

When did NASA first use synthetic vision to control a UAV?

It was in the X-38 project.

From *Ref 22*: "Virtual Cockpit Window" for a Windowless Aerospacecraft

Wednesday, January 01 2003

A software system processes navigational and sensory information in real time to generate a three- dimensional- appearing image of the external environment for viewing by crewmembers of a windowless aerospacecraft. The design of the particular aerospacecraft (the X-38) is such

that the addition of a real transparent cockpit window to the airframe would have resulted in unacceptably large increases in weight and cost.

When exerting manual control, an aircrew needs to see terrain, obstructions, and other features around the aircraft in order to land safely. The X-38 is capable of automated landing, but even when this capability is utilized, the crew still needs to view the external environment: From the very beginning of the United States space program, crews have expressed profound dislike for windowless vehicles. The well-being of an aircrew is considerably promoted by a three-dimensional view of terrain and obstructions. The present software system was developed to satisfy the need for such a view. In conjunction with a computer and display equipment that weigh less than would a real transparent window, this software system thus provides a "virtual cockpit window."

The key problem in the development of this software system was to create a realistic three-dimensional perspective view that is updated in real time. The problem was solved by building upon a pre-existing commercial program — LandForm C3 — that combines the speed of flight-simulator software with the power of geographic-information-system software to generate real-time, three-dimensional-appearing displays of terrain and other features of flight environments. In the development of the present software, the pre-existing program was modified to enable it to utilize real-time information on the position and attitude of the aerospacecraft to generate a view of the external world as it would appear to a person looking out through a window in the aerospacecraft. The development included innovations in realistic horizon-limit modeling, three-dimensional stereographic display, and interfaces for utilization of data from inertial-navigation devices, Global Positioning System receivers, and laser rangefinders. Map and satellite imagery from the National Imagery and Mapping Agency can also be incorporated into displays.

The Press Release from Rapid Imaging Software, Inc., which did the synthetic vision work for the X-38, states {*Ref. 23*}

On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as "the best seat in the house", the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight.

Other References cited by the AUVSI Authors

"Pathway-in-the-Sky Contact Analog Piloting Display," Knox and Leavitt, 1977

In the article the AUVSI Authors state in Paragraph 7:

In 1977, NASA researcher Charles Knox published "Pathway-in-the-Sky Contact Analog Piloting Display," which included a complete design for a synthetic vision system. It featured a computer that projected a 3D view of the terrain given an aircraft's position and orientation. This out-the-window perspective view was displayed on a CRT type display. Such displays were called "Pictorial Format" avionics systems, but we recognize them as containing all of the essential elements of a modern synthetic vision display.

The pictures that will be reproduced shortly are from the Knox report (Charles E. Knox and John Leavitt). I have placed them with the descriptions from Knox pages 3-4. The complete Knox report is *Ref. 24*.

Everything comes together in Knox Figure 4, which shows the Airplane track-angle pointer and scale, the Airplane symbol with shadow superimposed, the Flight-path-angle scale, the Flight-path prediction vector, the Earth horizon, the Roll pointer, the Airplane altitude deviation from path, the Airplane flight-angle bars, the Programmed path-angle indicator, the Potential flight-path-angle box, and the Programmed flight path.

The Programmed flight-path consists of two three-dimensional lines showing the predicted flight path of the airplane. Knox and Leavitt's work is significant but there is no terrain, there is no digital elevation database. There is no synthetic vision.

From Knox **Description of Path-in-the-Sky Contact Analog Piloting Display** *{Ref. 24}*:

Display Symbology

The format of the PITS contact analog display shows airplane attitude information in the form of bank angle and pitch changes. Airplane performance information is shown in the form of airplane flight-path angle and flight-path acceleration (which may be used as thrust- or energy-management control). Both vertical and lateral path deviations during a tracking task are shown in pictorial form.

Path-tracking situation information is shown through a combination of an airplane symbol, a vertical projection of the airplane symbol with an extended center line drawn at the altitude of the path, a flight-path predictor, and a drawing of the programed path (fig. 1). These four pieces of symbology are drawn in a perspective display format as if the observer's eye were located behind and above the airplane.

The airplane symbol is a tetrahedron with a smaller tetrahedron at the tail to visually enhance pitch changes. The airplane's true position with respect to the path is at the symbol's apex. The symbol rolls and pitches about its apex in accord with the real airplane's attitude.

The page number 23 is at the top.

Figure 1.- Path, shadow, flight-path predictor, and airplane symbology.

Altitude deviations from the programed path are indicated to the pilot pictorially by a vertical projection of the airplane symbol. The projection, drawn with dashed lines, may be thought of as a shadow; as shown in figure 2, it remains directly above or below the airplane at the altitude of the path. If the airplane is above the programed path, the shadow appears to be below the airplane symbol. If the airplane is below the programed path, the shadow appears to be above the airplane symbol.

(a) Above path.

(b) Below path.

Figure 2.- Airplane symbol and shadow interactions during altitude deviations.

Since the shadow is always drawn directly above or below the airplane symbol, the pilot may readily identify lateral tracking deviations when they are combined with a vertical tracking error. Figure 3 shows the perspective view of the shadow, the airplane symbol, and the path when the airplane is above and to the left of the path.

Figure 3.- Airplane above and to left of path.

Altitude deviations from the programed path are also shown to the pilot in numerical form in a box in the upper right-hand corner of the display (fig. 4). The pilot is expected to use this information when the path and shadow are out of the display field of view, such as could occur during initial path captures.

A flight-path prediction vector (fig. 4) in the horizontal plane is attached to the shadow. The prediction vector, indicated by a dashed line, shows the airplane's predicted path for the next 10 sec based on the airplane's present bank angle and ground speed. An extended shadow center line drawn from the apex of the shadow in the direction of the present track angle, is also shown to aid the pilot with the lateral tracking task.

Figure 4.- The PITS contact analog display symbology.

Figure 5 shows the flight-path prediction vector and the present track indicator with the airplane in a left bank of 13°.


Figure 5.- The PITS display concept showing airplane below path and climbing in a left bank of 13°.

"The Electronic Terrain Map: A New Avionics Integrator", Small, D.M., 1981

In the article the AUVSI Authors state in Paragraph 8:

> In 1979, the U.S. Air Force completed its "Airborne Electronic Terrain Map Applications Study" and in 1981 published "The Electronic Terrain Map: A New Avionics Integrator" describing how a computerized terrain database could be displayed as an out-the-window 3D view allowing the pilot to "see" even at night and in other limited visibility situations.

No, Small did not describe "how a computerized terrain database could be displayed as an out-the-window 3D view allowing the pilot to 'see' even at night and in other limited visibility situations."

The Small report discusses the concept of a digital Electronic Terrain Map (ETM) and proposes that it be used for:

1. Navigation;
2. Terrain Following/Terrain Avoidance (TF/TA);
3. Threat avoidance, analysis, warning, and display;
4. Terrain Masking;
5. Weapon delivery;
6. Route planning.

He does say, "An electronic map subsystem can generate perspective scenes, which are essentially computer generated images of the surrounding area, and an electronic map should be much easier to interpret," but:

1. The statement must be understood according to the meaning it would have had at the time the article was written (circa 1981); and

2. Wishing for a desired result is not the same as teaching how to do it.

This is what the Small report *{Ref. 25}* is about:

From the section INTRODUCTION:

INTRODUCTION

Currently, the Air Force has in the inventory paper and film map systems, which were developed to support the high and level flight environment. These maps were an effective means of tapping the vast files of information stored in the Defense Mapping Agency (DMA) data base, when the crew had time to study and interpret them (in fact, much of their value was actually obtained from pre-flight mission preparations). Interviews with pilots indicate that paper maps are less useful for low altitude flights. Film maps with CRT annotation are somewhat better, but still have a fundamental limitation in that it takes an operator to access any information. That is, it is not possible to transfer information directly from the data base to any other avionics system when it is stored on paper or film maps in what is essentially an analog form.

The map reading process is a demanding task that can be simplified by using a digital map subsystem which accesses the information needed and presents it in a form which can be easily interpreted. At low altitude, and with a line of sight limited to the next ridge line, it's very difficult to interpret standard paper maps, which are presented as a vertical projection of a large

area. <u>An electronic map subsystem can generate perspective scenes, which are essentially computer generated images of the surrounding area</u>, and an electronic map should be much easier to interpret. In addition, essential information from the map data base can be placed on the pilots Head Up Display, reducing the need for head down operations.

Paper maps are clumsy to use, whether you are flying an aircraft or driving a car. An electronic map, if properly done, would make using a map easier.

However, whether the map is electronic or on paper, you still have to know where you are. Small has not addressed that issue in this section.

The issue of what Small might mean by "perspective scenes" will be addressed later.

From the section FUTURE AIRCRAFT SYSTEM:

FUTURE AIRCRAFT SYSTEM

The purpose of adding an ETM subsystem to a future avionics suite is to provide map data and displays that can be interfaced with other subsystems to improve the performance of the <u>terrain following/terrain avoidance (TF/TA)</u>, <u>threat avoidance</u> and <u>navigation</u> avionics subsystems. The requirement for the simultaneous exchange of processed map data by three or four avionics subsystems will be the most difficult objective and important feature of the ETM. Development and incorporation of the advanced ETM concepts and technologies will be required to augment <u>future threat avoidance, navigation, TF/TA, and weapon delivery avionics subsystems</u>. Applications/examples of using these ETM concepts and/or technologies and the utilization of an ETM subsystem as a source of information follows.

TF/TA

The first example will be the automatic TF/TA avionics subsystem. <u>Our existing automatic TF subsystems operate using only active sensors as sources of terrain profile information (i.e. radar).</u> This makes the subsystem totally dependent on the limitations of this single information source. <u>In case of radar, range is limited to line of sight. Absolutely no information is available beyond line of sight.</u> This forces the TF subsystem to provide unnecessarily large clearances over ridges to avoid the following peak which may or may not be imminent. <u>Further, the TF subsystem must radiate on an almost continuous basis to provide a continuous terrain profile.</u> Consequently detection and jamming are TF subsystem vulnerabilities. <u>A digital terrain map could provide a second source of information to the TF flight command processing subsystem and the use of the map could serve as a backup in case of radar failures or jamming. The ETM could provide information concerning beyond line of sight conditions, enlarge the total field of view scanned for turning, and avoid the reduction of the duty cycle of the radar emission.</u> In fact, this ability to scan the terrain to the side without turning and looking beyond the line of sight makes it possible for the first time to consider true automation of the TA function. <u>Because of limitations in the existing DMA data base, the approach should be cautious and an active sensor will be needed to make absolute clearance measurements.</u> None the less, the application of stored data, to the TF/TA problem can potentially have tremendous impact on Air Force capabilities in the low altitude flight mission.

1. Existing Terrain Following systems use active radar to profile the terrain. The radar is line-of-sight, so it cannot see farther terrain hidden by closer terrain.

2. An Electronic Terrain Map would allow you to determine what is over the next ridge. However, "Because of limitations in the existing DMA data base, the approach should be cautious and an active sensor will be needed to make absolute clearance measurements.

You still need to know where you are so you can locate your position on the map.

THREAT AVOIDANCE

The second example will be the threat avoidance avionics subsystem. The whole purpose of low altitude missions is to reduce the probability of detection and attrition. If the threat avoidance problem is solved without regard to the location and lethal range of threats, the resultant path may place the aircraft in greater jeopardy than before. Terrain masking and launch dynamics limitations must be exploited to the fullest. Careful selection of the aircraft's routes to the target may be done by the crew or automatically. In either case, a digital map is required to provide the terrain information and the position of the threats identified by the avionics system. Pre-mission planning can provide a starting point for this analysis, but the dynamics of the threat assessment makes it essential that the crew be able to redefine the mission as new information is received from command and control functions or via the aircraft's own suite of threat defense sensors.

1. If you have a good terrain map you can use the terrain to hide your aircraft from those whom you do not want to know where you are or if you are even in the area.

2. If your terrain map shows you where the threats are, don't go there.

You still have to know your map position.

NAVIGATION

The third example will be the navigation avionics subsystem. With the addition of a correlator to the avionic suite and using the on-board sensors together with the ETM, navigation can be accomplished. Also, by displaying the ridge lines derived from stored terrain data on the head up display, passive navigation is possible. Hence, the ETM could also improve the utilization of the navigation subsystem.

Small does not say what he means by a "correlator" or which onboard sensors he would use them with.

There can be several types of "correlators."

1. You can visually look out your aircraft window at the terrain (mountains, lakes, rivers) and cultural features (towers, highways) and then look at a map and try to find them. Then you figure out where you would be on the map to see what you are seeing. The map can be paper or electronic. An example of a paper map converted to digital format is in _Ref 26_. This is part of the Washington Sectional Aeronautical Chart, Scale 1:500,000 55th Edition, published March 3, 1994 by U.S. Department of Commerce National Oceanic and Atmospheric Administration National Ocean Service. Click Here for map PDF. If

you are not familiar with the symbology used in paper sectional maps here is the Washington Legend.

If you use the Zoom and Pan features of Acrobat you will see the advantages of an electronic version of a paper map (i.e., a digital map).

2. You can use a computer to do the correlation, such as the method taught by Horn and Bachman in **Using Synthetic Images to Register Real Images with Surface Models.** *[Ref. 27]*

> Abstract: A number of image analysis tasks can benefit from registration of the image with a model of the surface being imaged. Automatic navigation using visible light or radar images requires exact alignment of such images with digital terrain models. In addition, automatic classification of terrain, using satellite imagery, requires such alignment to deal correctly with the effects of varying sun angle and surface slope. Even inspection techniques for certain industrial parts may be improved by this means.

Small has not mentioned *Terrain Referenced Navigation.* In Terrain Referenced Navigation a Radar or Lidar is used to take a few elevation measurements of the terrain. These measurements are matched to the terrain in a digital terrain elevation database.

An early example of Terrain Referenced Navigation is U.S. Patent 3,328,795 **Fixtaking Means and Method** issued June 27, 1967 to Hallmark. *[Ref 28]* From Column 2, lines 18-53:

> Previously proposed fixtaking and navigational systems have sought to utilize terrain elevation data, and they have been based upon the analog comparison of sample data which are the continuous, analog representation of continuous variations in terrain elevations, with similar data contained in contour maps employed as such. At least some of the sample and known data hence have always been graphically or photographically displayed on actual sheets of paper, rectangles of photographic film, etc., and the values represented thereby have been shown as physically measurable along at least two axes. Because of the nature of the data employed, cumbersome and unwieldly equipments for photographic development, superposition of map over map, orthogonal adjustments of one set of data relative to another, etc. have been unavoidable sources of added weight, complexity, error, and malfunction.

> The present invention does not employ continuously recorded, analog data, but has as one of its bases the use of quantized terrain altitude information taken at discrete points. A numerical comparison of sample and prerecorded data is performed at high speed, and with results predictable and repeatable for the same inputs, by a digital computer. Since the digital computer and associated components are relatively unaffected by noise, vibrations, nuclear radiation, etc., no equipment is required for performing two-dimensional data comparisons, and no feedback or nulling circuitry is needed for determining the point of best physical correlation of the sample with the pre-recorded data. As distinguished from systems utilizing analog information, the digital computer is free from the sources of error unavoidably present where analog comparisons are made and hence is not only more accurate but is able to tolerate relatively large errors in sample and known data values without compromising fixtaking accuracy.

TERCOM (Terrain Contour Matching) uses contour matching instead of elevations. **U.S. Patent 4,347,511 Precision navigation apparatus** issued August 31, 1982 to **Hofmann , et al.** *[Ref. 29]* mentions:

"Aviation Week & Space Technology", Feb. 25, <u>1974</u>, page 50, ff, discloses the *Tercom* process. In the latter, barometric measuring devices and radio altimeters produce altitude profiles during specific time intervals of a flight over characteristic terrain. The one-dimensional differential profile between the barometric altitude and altitude above ground is compared with a two-dimensional reference profile. Here, the measured altitude profile is adjusted until the best correlation is achieved, so that the exact position of the aircraft results.

There are some problems with Terrain Referenced Navigation and Tercom:

1. They are not reliable if the terrain changes after the Digital Terrain Map is made. Terrain can change seasonally due to snow accumulations or permanently due to vegetation growth (trees) or new buildings (technically, a cultural feature).

2. They do not work over large flat terrain. *{See Ref. 30}*

3. They do not work over bodies of water.

Although Terrain Referenced Navigation and Tercom systems that use Radar or Lidar still send out signals that can be detected, the signals are far less detectable than the signals used in Small's description of TF/TA systems. Small's TF/TA system uses a radar to scan the terrain, which is why it cannot see beyond the next ridge.

Small's omission of Terrain Referenced Navigation and Tercom is puzzling.

Small gives a choice between Radar-scanned terrain and finding your location on a map using an undefined method of adding a correlator to the avionic suite and using the on-board sensors together with the Electronic Terrain Map (ETM).

What did Small mean when he said, "An electronic map subsystem can generate perspective scenes, which are essentially computer generated images of the surrounding area, and an electronic map should be much easier to interpret?"

In the 1980s (and well into the 1990s) the conventional wisdom was that Real 3D graphics was too computationally intensive to do in real time without large and very expensive hardware.

Honeywell was the leader in avionics. Harris was probably a close second. They both spent the 1980s and 1990s competing with each other to see who could do the best fake 3D.

For example, U.S. Patent 4,660,157 **Real time video perspective digital map display method** issued April 21, 1987 to Beckwith, et al. *{Ref. 31}*

Instead of mathematically rotating the points from the database the '157 Patent accounts for the aircraft's heading by controlling the way the data is read out from the scene memory. Different heading angles result in the data being read from a different sequence of addresses.

From Column 3, lines 21 - 38:

> The addresses of the elevation data read out of the scene memory representing points in the two-dimensional scene of the terrain are then transformed to relocate the points to positions where they would appear in a perspective scene of the terrain. Thus, each point in the two-dimensional

scene is transformed to its new location in the perspective scene to be displayed on the viewing screen, and in the process, the data is automatically oriented with a heading-up disposition. The transformed points are then stored in a speed buffer for further processing by sun angle and line writing logic prior to being stored in a display memory from which data is read out to the display screen. Since data in the display memory represents one-to-one data to be displayed on the CRT, this data will be referred to as pixels (picture elements) in terms of its storage in the display memory for transfer to the CRT display.

The '157 patent accounts for the roll attitude of the aircraft by mathematically rotating the screen data after it is projected. From Column 12, lines 42 - 47:

> The points which are output by the perspective transform circuit 110 are supplied to a screen rotation circuit 120 which serves to rotate the display data in accordance with the roll of the aircraft so that the display will accurately depict the view as it would appear, if visible, through the window of the aircraft.

Beckwith displays only points.

Fake 3D + Only Points does not qualify as what is now considered synthetic vision.

There is Honeywell's U.S. Patent 5,179,638 **Method and apparatus for generating a texture mapped perspective view** issued January 12, 1993 to Dawson, et al. *(Ref. 32)*

It even has the word "perspective" in the title, but the perspective it produces is a trapezoidal perspective, not a real 3D projected perspective.

Dawson '638 incorporates by reference a number of other patents and patent applications, and determining exactly what Dawson meant in '638 requires following a trail through these patents. The short version is that what Dawson means by "perspective" is contained in U.S. Patent 4,884,220 **Address Generation with Variable Scan Patterns** issued November 28, 1989 to Dawson (again), *(Ref. 33)* which is incorporated by reference by Dawson '638.

After discussing the shortcomings of prior art, Dawson '220 says (Column 2, line 56 through Column 3, line 2):

> This invention differs from the prior methods of perspective view generation in that a trapezoidal scan pattern is used instead of the radial scan method. The trapezoidal pattern is generated by an orthographic projection of the truncated view volume onto the cache memory (terrain data). The radial scan concept is retained, but used for an intervisibility overlay instead of the perspective view generation. The radial scan is enhanced to include a full 360 degree arc with programmable attributes. The rectangular pattern retains the parallel scan methodology for plan view map generation. Both a nearest neighbor and a full bilinear interpolation method of scan address generation are implemented.

And now we know what Dawson means by "perspective."

A real 3D perspective is a 3D projection.

Anything else is Fake 3D.

If you think Fake 3D is just as good as Real 3D then the next time someone owes you money tell them that it's ok to pay you in fake dollars.

There is also the matter that Small is only wishing for a desired result. Wishing for a desired result is not the same as teaching how to do it.

Not only did Small not teach it, he was not clear in saying what he was wishing for.

VCASS: An Approach to Visual Simulation, Kocian, D., 1977

In the article the AUVSI Authors state in Paragraph 6:

> This emergence of computer flight simulation in the 1970s appears to have sparked a monumental amount of research. The U.S. Air Force began its Visually Coupled Airborne Systems Simulator (VCASS) program, with a particular eye toward future-generation fighter aircraft ("VCASS: An Approach to Visual Simulation," Kocian, D., 1977).

The Kocian report is available in _Ref. 34_.

Summary

Kocian is about using a Helmut Mounted Display (HMD) with a Head Position Sensing System to replace large expensive hemispherical display systems used in simulators. The simulator is used to develop the visual interface used by crew members to control advanced weapon systems. This visual interface can then be used in airborne operations.

During simulation a representative visual scene is generated by the graphics or sensor imagery generators but, from Paragraph 11 (emphasis added):

> **For an airborne VCASS capability, it is only necessary to install the VCS components along with a small airborne general purpose computer in a suitable aircraft and interface a representative programmable symbol generator to an on-board attitude reference system in order to synthesize either airborne or ground targets.**

The airborne version does not synthesize a visual scene, so it is not synthetic vision.

Details

A Visually-Coupled System is one that visually couples the operator to the other system components through the use of a Helmut Mounted Display (HMD) and Helmut Position Sensor. From Paragraph 9:

> The key components of VCASS will be VCS hardware which includes the HMS and HMD. These components are used to "visually-couple" the operator to the other system components he is using. AMRL has pioneered efforts in the research, development and testing of these hardware techniques.

A system using a Helmut Mounted Display with a Helmut Position Sensor is less expensive than the hemispherical projection systems being used and produces better results. Paragraph numbers have been added to the following paragraphs from Kocian.

[1]   In recent years Air Force operational units have experienced a continuing trend downward in the number of flight hours in aircraft that can be provided to each individual pilot for training and maintaining proficiency. This comes at a time when aircraft systems are becoming ever more complex and sophisticated requiring comparatively more hours for training to maintain the same relative flying proficiency. With increasing costs for fuel and aircraft and the failure of DoD funding to keep pace with these costs, the trend is almost sure to continue. In adjusting to the realities of keeping overall experience at a satisfactory level and reducing costs, procurement of aircraft simulators has become a necessity.

[2]   The rapid proliferation of simulators with no standard technical criteria as a guide has resulted in the evolution of several different design approaches. Most existing visual scene simulators utilize electro-optical devices which project video imagery (generated from a sensor scan of a terrain board or a computer generated imagery capability) onto a hemispherical dome or set of large adjacent CRT displays arranged in optical mosaics with the weapon, vehicle, and threat dynamics being provided by additional computer capabilities.

[3]   These large fixed-base simulators suffer from the following drawbacks. The majority of the visual projection techniques used in these simulators do not incorporate infinity optics which provide collimated visual scenes to the operator. Those which do are large and expensive and incorporate large CRT displays. The luminance levels and resolution of these displays are usually low and do not represent true ambient conditions in the real environment. Additionally, hemispherical infinity optics are difficult to implement and this technique requires excessive computer capacity to generate imagery due to the need for refreshing an entire hemisphere instantaneously, regardless of where the crew member is looking. In this regard, existing computer capability is not used effectively to match the channel capacity of the human visual system. There are also generally no stereoscopic depth cues provided for outside of-cockpit scenes. Another important drawback to these simulators is that the visual simulation is not transferrable to the actual flight environment, i.e., the ground-based system cannot be transferred to an actual aircraft to determine simulation validity. Finally, most existing techniques are very expensive and do not allow the flexibility of incorporating other display design factors such as different head-up display image formats, fields-of-view (FOV), representative cockpit visibilities, and optional control and display interfaces.

[4]   A quite different approach to solving the visual presentation problems of aircraft simulators is to employ the use of visually coupled systems (VCS). For many years it has been the mission of the Aerospace Medical Research Laboratory to optimize the visual interface of crew members to advanced weapon systems. This mission has been primarily pursued in two areas: (1) the establishment of control/display engineering criteria; and (2) the prototyping of advanced concepts for control and display interface. An important part of fulfilling this mission has been the development of VCS components which includes head position sensing systems or helmet mounted sights (HMS), eye position sensing systems (EPS) and helmet mounted displays (HMD).

363636

363636

3636

363636363636

3636363636363636363636

3636363636363636363636363636

3636363636363636

During simulation a representative visual scene is generated by the graphics or sensor imagery generators. From Paragraph 7:

> A more detailed analysis of the problem has produced a set of characteristics which a more ideal aircraft simulator might possess. <u>Of primary importance is that it should be a flexible visual scene simulation providing synthesized out-of-the-cockpit visual scenes and targets</u>, a representative vehicle whose type can be altered, threat and weapon dynamics, flexibility of control and display configurations, and inputs from sensor or real world imagery. It should be portable if possible and provide alternatives for crew station display options including number and configuration. <u>This simulator</u> should also be useable in both simulated air-to-ground weapon delivery and air-to-air engagement scenarios. <u>Finally, it should be possible to use the same system in ground fixed base and motion base simulators as well as in aircraft.</u>

However, the airborne version does not synthesize the out-the-cockpit visual scene. It only displays the symbols used in its role as a weapons controller. That is why the airborne version only needs a small airborne general purpose computer. From Paragraph 11 (emphasis added):

> **For an airborne VCASS capability, it is only necessary to install the VCS components along with a <u>small airborne general purpose computer</u> in a suitable aircraft and interface a representative programmable <u>symbol generator</u> to an on-board attitude reference system <u>in order to synthesize either airborne or ground targets</u>.** This approach has the ultimate flexibility of utilizing the same <u>symbol set</u>, threat dynamics, etc., in the air that were originally used in the ground simulation. In either case, the crew member will engage electronic targets (either air-to-air or air-to-ground) and launch electronic weapons. His performance in these tasks in turn will be recorded and assessed for performance or utilized as training aids for the crew member or operator.

The airborne version does not synthesize a visual scene, so it is not synthetic vision as the term is now used.

In addition, the Kocian report describes a work-in-progress. From Paragraph 19:

> <u>The design considerations involved in building a helmet-mounted display for the VCASS simulation present a more formidable and subjective set of problems whose solution is not entirely clear</u>. It is certain that a larger display field-of-view is required but how large remains an unanswered question. The optical physics that are part of the display design imposed constraints which are difficult to resolve. Currently, an interim display possessing a 60 degree instantaneous field-of-view is planned for the VCASS; however, recent studies have shown that this may not be large enough especially when viewed with one eye. This leads naturally to biocular or binocular configurations. A whole host of human factors problems then becomes important including brightness disparity, display registration, and eye dominance. <u>The decision whether or not to include color also becomes a major design decision</u> not only because of the engineering development required but because user acceptance may weigh heavily on this factor.

(The question whether or not to use color was later settled. The answer was color.)

U.S. Patent 5,566,073 Pilot Aid Using A Synthetic Environment
issued October 15, 1996 to Margolin

This patent was not mentioned by the AUVSI Authors.

Abstract

A pilot aid using synthetic reality consists of a way to determine the aircraft's position and attitude such as by the global positioning system (GPS), a digital data base containing three-dimensional polygon data for terrain and manmade structures, a computer, and a display. The computer uses the aircraft's position and attitude to look up the terrain and manmade structure data in the data base and by using standard computer graphics methods creates a projected three-dimensional scene on a cockpit display. This presents the pilot with a synthesized view of the world regardless of the actual visibility. A second embodiment uses a head-mounted display with a head position sensor to provide the pilot with a synthesized view of the world that responds to where he or she is looking and which is not blocked by the cockpit or other aircraft structures. A third embodiment allows the pilot to preview the route ahead or to replay previous flights.

It teaches what is now known as synthetic vision in sufficient detail that it may be practiced by a *Person having Ordinary Skill In The Art* without undue experimentation. A Person having Ordinary Skill In The Art (POSITA) is a legal term that is often fought over during patent litigation.

This patent is a continuation of Application Ser. No. 08/274,394, filed Jul. 11, 1994, which is its filing priority date. The earliest known description of the invention is in *Ref. 35*.

For those unfamiliar with Patent Law, the Claims are the legal definition of the invention. The purpose of the Abstract is to provide search terms only.

See *Ref. 36* for the patent. (I am the inventor named in the patent.)

U.S. Patent 5,904,724 Method and apparatus for remotely piloting an aircraft
issued May 18, 1999 to Margolin

This patent was also not mentioned by the AUVSI Authors.

Abstract

A method and apparatus that allows a remote aircraft to be controlled by a remotely located pilot who is presented with a synthesized three-dimensional projected view representing the environment around the remote aircraft. According to one aspect of the invention, a remote aircraft transmits its three-dimensional position and orientation to a remote pilot station. The remote pilot station applies this information to a digital database containing a three dimensional description of the environment around the remote aircraft to present the remote pilot with a three dimensional projected view of this environment. The remote pilot reacts to this view and interacts with the pilot controls, whose signals are transmitted back to the remote aircraft. In addition, the system compensates for the communications delay between the remote aircraft and the remote pilot station by controlling the sensitivity of the pilot controls.

It teaches the use of synthetic vision (as the term is currently used) for remotely piloting an aircraft. It teaches it in sufficient detail that it may be practiced by a Person having Ordinary Skill In The Art without undue experimentation.

This patent was filed January 19, 1996, which is its priority date.

For those unfamiliar with Patent Law, the Claims are the legal definition of the invention. The purpose of the Abstract is to provide search terms only.

See *Ref. 37* for the patent. (I am the inventor named in the patent.)

U.S. Patent Application Publication 20080033604
System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace

In the interests of full disclosure I have the following patent application pending: U.S. Patent Application Publication 20080033604 **System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace.**

Abstract

A system and method for safely flying an unmanned aerial vehicle (UAV), unmanned combat aerial vehicle (UCAV), or remotely piloted vehicle (RPV) in civilian airspace uses a remotely located pilot to control the aircraft using a synthetic vision system during at least selected phases of the flight such as during take-offs and landings.

See *Ref. 38* for the published patent application. (I am the inventor named in the application)

The Future of Synthetic Vision

This is what the AUVSI Authors have said about synthetic vision [Paragraph 2]:

> More recently it has evolved away from being a piloting aid to a potentially powerful tool for sensor operators.

and [Paragraph 22]:

> The recent availability of sophisticated UAS autopilots capable of autonomous flight control has fundamentally changed the paradigm of UAS operation, potentially reducing the usefulness of synthetic vision for supporting UAS piloting tasks. At the same time, research has demonstrated and quantified a substantial improvement in the efficiency of sensor operations through the use of synthetic vision sensor fusion technology. We expect this to continue to be an important technology for UAS operation.

While I have no doubt that synthetic vision is very useful to the sensor operator, the news that its use in piloting UAVs is on its way out came as a big surprise to me.

The AUVSI Authors have an ulterior motive in making the statements. Their real objective is to make people believe synthetic vision no longer has value in controlling Remotely Piloted Vehicles (aka UAVs) and that a Remotely Piloted Vehicle that is flown using an Autonomous control system is no longer a remotely piloted vehicle and therefore a sensor operator may use synthetic vision without infringing U.S. Patent 5,904,724. See *Ref. 39* for the response Rapid Imaging Software's attorney sent to Optima Technology Group in 2006.

The statements made by the AUVSI Authors form a distinction without a difference unless there is a wall between the sensor operator and the pilot that results in the sensor operator having no influence on how or where the UAV is flown.

Consider the following scenarios:

1. The human sensor operator has synthetic vision; the human pilot does not. No communications is allowed between the human sensor operator and the human pilot lest the human sensor operator influence the human pilot where or how to fly the aircraft. Otherwise, it might be considered as contributing to piloting the aircraft. This results in a decidedly sub-optimal system.

2. The human sensor operator has synthetic vision; the aircraft is flown autonomously (a machine pilot). No communications is allowed between the human sensor operator and the machine pilot lest the human sensor operator influence the machine pilot where or how to fly the aircraft. Otherwise, it might be considered as contributing to piloting the aircraft. This also results in a decidedly sub-optimal system.

There are legal and political ramifications to this scenario.

Someone has to be responsible for the operation and safety of the flight. The FAA defines "Pilot in Command" as *[Ref. 5]*:

> *Pilot in command* means the person who:
>
> (1) Has final authority and responsibility for the operation and safety of the flight;
> (2) Has been designated as pilot in command before or during the flight; and

(3) Holds the appropriate category, class, and type rating, if appropriate, for the conduct of the flight.

It is unlikely that FAA will allow this responsibility to be delegated to a machine anytime soon. That's where the political ramifications come in. A UAV (especially a completely autonomous UAV) that injures or kills civilians would ignite a political firestorm that would ground the entire UAV fleet.

Since there must be a human in the loop to be responsible for the operation and safety of the flight, that leaves a system where:

1. The human sensor operator has synthetic vision;

2. The pilot is a machine;

3. The operation and safety of the flight is held by a human (different from the sensor operator) who is designated the Pilot-in-Command;

4. No communications is allowed between the human sensor operator and the machine pilot or the human sensor operator and the human Pilot-in-Command lest the human sensor operator influence the machine pilot or the human Pilot-in Command where or how to fly the aircraft. Otherwise, it might be considered as contributing to piloting the aircraft. This also results in a decidedly sub-optimal system.

Frankly, it is stupid to cripple the utility of a UAV system in order to avoid paying a small patent licensing fee. Besides, the '724 patent is for the use of synthetic vision in a Remotely Piloted Aircraft. It is not limited to the use of synthetic vision by the crew member designated as the Pilot.

An autonomous pilot would have to be really good.

Even after 100 years of aviation, pilots still encounter situations and problems that have not been seen before. The way they deal with new situations and problems is to use their experience, judgment, and even intuition. Pilots have been remarkably successful in saving passengers and crew under extremely difficult conditions such as when parts of their aircraft fall off (the top of the fuselage peels off) or multiply-redundant critical controls fail (no rudder control). Computers cannot be programmed to display judgment. They can only be programmed to display judgment-like behavior under conditions that have already been anticipated. UAVs should not be allowed to fly over people's houses until they are at least smart enough to turn on their own fuel supply.

[On Apr. 25, 2006 the Predator UAV being used by the U.S. Customs and Border Protection agency to patrol the border crashed in Nogales, Ariz. According to the NTSB report (NTSB Identification CHI06MA121) when the remote pilot switched from one console to another the Predator was inadvertently commanded to shut off its fuel supply and "With no engine power, the UAV continued to descend below line-of-site communications and further attempts to re-establish contact with the UAV were not successful." In other words, the Predator crashed because the system did not warn the remote pilot he had turned off the fuel supply and it was not smart enough to turn its fuel supply back on. (Ref. 40)]

An autonomous UAV assumes the computer program has no bugs.

Complex computer programs always have bugs no matter how brilliant or motivated the programmer(s). As an example, look at almost every computer program ever written.

An autonomous Unmanned Combat Aerial Vehicle (UCAV) will have little chance against one flown by an experienced pilot using Synthetic Vision until Artificial Intelligence produces a sentient, conscious

Being. At that point, all bets will be off because a superior sentient artificial Being may decide that war is stupid and refuse to participate. It may also decide that humans are obsolete or are fit only to be its slaves.

I propose yearly fly-offs:

1. A UCAV flown and fought autonomously against an F-22 (or F-35).

2. A UCAV flown and fought by a human pilot using synthetic vision against an F-22 (or F-35).

3. A UCAV flown and fought by a human pilot using synthetic vision against a UCAV flown and fought autonomously.

And that is the future of Unmanned Aerial Systems.

References

Reference 1 - *Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward* by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun, AUVSI's **Unmanned Systems**, December 2008, pages 27-28.

This article has been reproduced with the permission of the Association for Unmanned Vehicle Systems International (AUVSI), which is the world's largest non-profit organization devoted exclusively to advancing the unmanned systems community. AUVSI, with members from government organizations, industry and academia, is committed to fostering, developing, and promoting unmanned systems and related technologies. http://www.auvsi.org/

PDF: http://www.jmargolin.com/svr/refs/ref01_auvsi.pdf

For the purposes of this response the article has been converted to text and the paragraphs have been numbered for easy reference: http://www.jmargolin.com/svr/refs/ref01_auvsi.htm

.

Reference 2 – U.S. Patent 5,593,114 **Synthetic Vision Automatic Landing System** issued January 14, 1997 to Ruhl (Assignee McDonnel Douglas Corporation).

Html copy at USPTO Patent Database:
http://patft.uspto.gov/netacgi/nph-
Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1
&f=G&l=50&s1=5,593,114.PN.&OS=PN/5,593,114&RS=PN/5,593,114

PDF copy (complete with drawings): http://www.jmargolin.com/svr/refs/ref02_5593114.pdf

Reference 3 - **Synthetic Vision Technology Demonstration, Volume 1 of 4, Executive Summary**; Synthetic Vision Program Office Federal Aviation Administration; Malcolm A. Burgess, FAA; Terence Chang, TRW; Dale E. Dunford, USAF; Roger H. Hoh, Hoh Aeronautics; Walter F. Home, GTRI; Richard F. Tucker, TRW; December 1993. http://www.dtic.mil/srch/doc?collection=t2&id=ADA280564

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref03_old_faa_1993.pdf

Reference 4 – **Multi-Crew Pictorial Format Display Evaluation; AFWAL-TR-87-3047**;
T.C. Way, R.L. Martin, J.G. Gilmour, M.E. Hornsby, R.E. Edwards; Final Report For Period May 1984 – January 1987, Boeing Military Airplane Company, February 1987.
http://handle.dtic.mil/100.2/ADA189349

Mirrored copy: http://www.jmargolin.com/svr/refs/ref04_pictorial_format.pdf

Reference 5 – **FAA current definition of Synthetic Vision**

FAA Title 14 Part 1

The FAA definition of synthetic vision from: http://ecfr.gpoaccess.gov/cgi/t/text/text-idx?c=ecfr&sid=41b1c51ea8ec4c9d1c5ebb94bbf28138&rgn=div8&view=text&node=14:1.0.1.1.1.0.1.1&idno=14

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref05_faa.pdf

> **Title 14: Aeronautics and Space**
>
> PART 1—DEFINITIONS AND ABBREVIATIONS
>
> <u>Synthetic vision</u> means a <u>computer-generated</u> image of the external scene topography from the <u>perspective of the flight deck</u> that is derived from <u>aircraft attitude, high-precision navigation solution,</u> and <u>database of terrain</u>, obstacles and relevant cultural features.
>
> Synthetic vision system means an electronic means to display a synthetic vision image of the external scene topography to the flight crew.

Reference 6 – FAA Synthetic Vision is based on the use of a Digital Elevation Database

FAA SV Issues- Part 23 Position
http://www.faa.gov/aircraft/air_cert/design_approvals/transport/media/Pt23ApproachSlides.pdf

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref06_Pt23ApproachSlides.pdf

Federal Aviation Administration Part 23 Synthetic Vision Approval Approach
Presentation to: FAA Synthetic Vision Workshop
Name: Lowell Foster
Date: Feb 14, 2006

Page 13:
> **SV Issues - Part 23 Position**
> **Terrain Data Confidence Issues Cont.**
>
> • Complete database accuracy impossible to validate
>
> • <u>**Everyone gets their data from the same original source**</u>
>
> • Manufacturers are doing everything possible to verify the current data is accurate, but that is really just a confidence builder
>
> <u>**If accuracy of data base must be validated then SV is unapproveable.**</u>

Page 14:

> **PositionRisk Management / Mitigation of Terrain Uncertainties**

•No operational credit for SV –current minimums still apply

•Significant safety benefits possible –outweighs what we consider minimal risk

•Experience -large data base errors to date have been easy to recognize and report –very visible on PFD and map display

•Small data base errors such as an elevation point are likely to be insolated, so exposure to a misleading information situation is considered small

•**Current resolution tends to round-up the elevation data** so that small errors are not as significant and on the conservative side

Reference 7 – Digital Elevation Model: http://data.geocomm.com/dem/

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref07_usgs_dem.pdf

The USGS Digital Elevation Model (DEM) data files are digital representations of cartographic information in a raster form. DEMs consist of a sampled array of elevations for a number of ground positions at regularly spaced intervals. These digital cartographic/geographic data files are produced by the U.S. Geological Survey (USGS) as part of the National Mapping Program and are sold in 7.5-minute, 15-minute, 2-arc-second (also known as 30-minute), and 1-degree units. The 7.5- and 15-minute DEMs are included in the large scale category while 2-arc-second DEMs fall within the intermediate scale category and 1-degree DEMs fall within the small scale category - (Source: USGS)

Reference 8 – Digital Elevation Database improved by a Space Shuttle mission.

http://spaceflight.nasa.gov/shuttle/archives/sts-99/

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref08_sts99.pdf

STS-99 Crew Works in Shifts to Complete Mapping Mission

Endeavour's international crew of seven spent 11 days in orbit during February 2000 mapping the Earth's surface with radar instruments.

.

.

.

Space Shuttle Endeavour Maps the World in Three Dimensions
The main objective of STS-99 was to obtain the most complete high-resolution digital topographic database of the Earth.

The Shuttle Radar Topography Mission, or SRTM, was an international project spearheaded by the National Imagery and Mapping Agency and NASA, with participation of the German Aerospace Center, DLR. SRTM consisted of a specially modified radar system that flew onboard

the space shuttle during STS-99. This radar system gathered data that produced unrivaled 3-D images of the Earth's surface.

Reference 9 – Honeywell IFPD Synthetic Vision System

http://www.honeywell.com/sites/portal?page=ipfd_primus&smap=aerospace&theme=T5

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref09_honeywell.pdf

Reference 10 - NASA description of the HiMAT project:

http://www.nasa.gov/centers/dryden/news/FactSheets/FS-025-DFRC.html

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref10_nasa_himat.pdf

Reference 11 - **Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display,** Shahan K. Sarrafian

NASA Technical Memorandum 84916 (May 1984):
http://www.nasa.gov/centers/dryden/pdf/87968main_H-1205.pdf
http://www.jmargolin.com/svr/refs/ref11a_sarrafian.pdf

NASA Technical Memorandum 85903 (August 1984):
http://www.nasa.gov/centers/dryden/pdf/87986main_H-1246.pdf
http://www.jmargolin.com/svr/refs/ref11b_sarrafian.pdf

I converted this article to text in order to make it easier to search and to quote from.
http://www.jmargolin.com/svr/refs/ref11c_sarrafian.doc . The downloaded PDF file is the controlling version.

47

Reference 12 - NASA Aviation Navigation
Tutorial: http://virtualskies.arc.nasa.gov/navigation/tutorial/tutorial3.html
Mirrored copy: http://www.jmargolin.com/svr/refs/ref12_nasa_ils.pdf

Reference 13 – THE ROLE OF SIMULATION IN THE DEVELOPMENT AND FLIGHT TEST OF THE HiMAT VEHICLE , M. B. Evans and L. J. Schilling, NASA-TM-84912, April 1984
http://www.nasa.gov/centers/dryden/pdf/87962main_H-1190.pdf

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref13_evans_schilling.pdf

From PDF page 13:

Visual Landing Aid

Actual. - Cues to the pilot during landing included the cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

Simulation model. - For most of the program, the landing cues for the pilot in a HiMAT simulation included only the instruments, mapboards, and the ILS/glideslope error indicators. Although these are all valid cues, they could not achieve the same effect as the television transmission used in actual flight. During flight, as soon as the pilot can identify the runway, his scan focuses more on the television picture and less on the cockpit instruments. To help alleviate this lack of fidelity in the simulation, a display of the runways on the dry lakebed was developed on a recently purchased Evans and Sutherland Graphics System.

Reference 14 - **Visual-Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles,** Reed, 1977, **AFHRL-TR-77-57**
http://www.dtic.mil/srch/doc?collection=t2&id=ADA049706
http://handle.dtic.mil/100.2/ADA049706

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref14_reed.pdf

Page 5 (PDF page 8):

VISUAL PROPRIOCEPTIVE CUE CONFLICTS IN THE CONTROL OF REMOTELY PILOTED VEHICLES

I. INTRODUCTION

An investigation was made of operator tracking performance under conditions of visual proprioceptive conflict. (The term *proprioception* as used here refers to sensations arising from the receptors of the nonauditory labyrinth of the inner ear and from muscles, tendons, and joints. Kinesthesis refers to sensations of movement arising from the receptors other than the nonauditory labyrinth.) The experimental scenario is described as follows: An operator is asked to maneuver a remotely piloted vehicle (RPV) from an airborne control station (a mother ship). This station is equipped with a television monitor, control stick, and other controls and displays necessary to maneuver the RPV through a specified

00301

course. The RPV, containing a television camera mounted in its nose, relays an image of the terrain to be displayed on the television monitor in the control station. Thus, the visual scene displayed to the operator represents the scene viewed by the camera. The task of the operator is to use the controls and displays to "fly" the RPV in much the same way he would fly a conventional aircraft.

The scenario is complicated by several factors. First, the visual inputs to the operator from the RPV are independent of the motion inputs from the control station. Thus, the operator will experience motion cues that are uncorrelated with the visual inputs received from the RPV. Second, while traditional pilot training programs operate on the philosophy that proprioceptive cues provided by the motion of the aircraft should be disregarded, research has shown that these cues are compelling, not easily ignored, and may improve performance when used in training simulators (see, for example, Borlace, 1967; Cohen, 1970; Douvillier, Turner, McLean, & Heinle, 1960; Fedderson, 1961; Huddleston & Rolfe, 1971; Rathert, Creer, & Douvillier, 1959; Ruocco, Vitale, & Benfari, 1965). The task simulated in the experiment presented here, however, required that the RPV operator disregard sensations of motion in order to maintain adequate performance. Under conditions of visual -proprioceptive conflict (as when the mother ship and/or the RPV are in turbulence) the stereotypic responses of pilots to correct angular accelerations will be inappropriate.

The objectives of the experiment were to obtain data applicable to the following.

1. The relative difficulty of controlling an RPV from an airborne station under different visual-motion combinations (e.g., visual-motion combinations that produce conflict, or no conflict).

2. The relative ability of pilots, navigators, and nonrated Air Force officers to operate an RPV from an airborne station (i.e., the effect of previous experience).

3. The differential effects of experience on the acquisition of skills necessary to operate an RPV.

4. Selection and training of potential RPV operators.

5. The need for motion in RPV training simulators.

II. METHOD

Simulation System

This research utilized the Simulation and Training Advanced Research System (STARS) facility of the Advanced Systems Division, Air Force Human Resources Laboratory, Wright Patterson Air Force Base, Ohio. The equipment consisted of an operator station mounted on a motion platform, hydraulic pump, terrain model, television camera and optical probe, experimenter station, and a Sigma 5 digital computer. A brief description of the hardware system is presented as follows.

Operator station. The operator station, illustrated in Figure 1, was designed to simulate the environment of an airborne control station. This station contained a television monitor that provided visual images relayed to h from a simulated RPV. These visual images were generated from a television camera and optical probe, which viewed the terrain model. The path followed by the camera and probe over the terrain model was commensurate with the vehicle flight path as determined by control stick

inputs provided by the subject. Since the control stick and visual system were independent of the motion platform, the capability existed for the subject to

5

[Figure 1. Operator station mounted on motion platform. *{not usable}}*]

maneuver the simulated RPV under various environmental conditions. This arrangement permitted the introduction of conditions in which the RPV alone, the airborne station alone, or both, were under air turbulence.

The subject sat in an aircraft-type seat directly facing a 14- by 11-inch (35.6 by 27.9 cm) television monitor, which was mounted in a center sectional panel of the operator console. The distance between the subject's eyes and the center of the television screen was 28 inches (71.1 cm). The viewing angle subtended 28.07° in the lateral plane and 22.23° in the vertical plane of the monitor. An altimiter, altitude warning light, and an attitude director indicator (ADI) were mounted on a flat sectional panel to the left of the subject and at an angle of 45° from the center panel (See Figure 2). The altimeter was a vertical straight-scaled indicator with a moving pointer that provided altitude readings in feet above sea level. An amber altitude warning light flashed whenever the simulated RPV altitude dropped to a level, below 180 feet (54.9 m), remained on whenever altitude exceed 1,000 feet (304.8 m) and was off between 180 and 1,000 feet.

A 6-inch (15.2 cm) side-arm rate control stick was mounted on the right-hand side console armrest (see Figure 2). The control was a spring-centered stick with a dual-axis (fee positioning) capability that required 4 ounces, (113.4 g) breakout force. The same amount of force was needed to hold the stick at full deflection. The range of deflection on both lateral (right - left) and longitudinal (fore - aft) stick was 0 to 25° (henceforth referred to as 0 to 100 percent deflection).

In addition, the operator station contained a foot switch to allow the subject to communicate with the experimenters. White noise was input to the subject's headset to mask external disturbances. The aircraft seat was equipped with a standard harness and lapbelt to protect the subject. An air conditioner maintained the station at 70° F (21.1° C). Finally, incident illumination was at an average of .37 footcandles at eye level.

6

[Figure 2. Operator station instruments and control stick. {not usable}]

Motion system. The operator station was mounted on a motion platform that provided onset cues in two degrees of freedom of angular acceleration. Roll onset cues were provided by tilting the simulator about the longitudinal axis (i.e., the X axis) and pitch onset cues were provided by tilting the simulator about the lateral axis (i.e., the 'Y' axis). Motion was achieved by actuation of hydraulic cylinders mounted under the 9- by 8-feet (2.74 by 2.4 m) simulator platform, as shown in Figure 1.

Visual system. The visual system consisted of a three-dimensional terrain model (a modified SMK-23 Visual Simulator, The Singer Company), television camera and optical probe, and three monochromatic television monitors. The terrain model provided "real-world ground cues for visual tracking over the surface. The real-world to terrain model scale was 3,000:1 and represented a six by twelve-mile (9.65 by 19.3 km) area. The model was mounted on an endless belt that was servo-driven to represent the continuous changes in scene as the simulated RPV traveled along north-south directions. A television camera viewed the terrain model through an optical probe that contained a servoed mechanical

assembly to permit the introductions of heading, roll, and pitch. Both the camera and probe were mounted on a servo-driven carriage system that moved across the terrain model to simulate movement of the RPV along east-west directions and in and out to simulate altitude changes. The field of view represented on the television monitor subtended a viewing angle of 50° horizontally and 38° vertically over the terrain model. One television monitor was mounted in the operator station and the other two were located in the experimenter station. All three monitors had a 1,000-line resolution vertically.

Experimenter station. The experimenter station contained the equipment necessary to monitor the status of the hardware/software and control activities of the subject, and to setup the various stimulus conditions. This station was manned by two experimenters. The task of the first was to prepare the system for operation, insure that all hardware was operating effectively and reliably prior and during the experiment, and set up the conditions for all experimental trials in accordance with a prepared check list. The task of the second experimenter was to determine the appropriate time for introducing specific stimuli to the subject. When certain criteria were met, the experimenter pressed a discrete hand-held insert button to initiate a stimulus trial.

Computer system and interfaces. A Sigma 5 digital computer was used to drive the peripkeral equipment, and to record data during experimental runs. Resident software consisted of a real-time aerodynamic mathematical model, executive routine, and data recording programs. The

7

Reference 15 - Lunar Driving Simulator History
http://www.knology.net/~skeetv/SimHist3.html

Mirrored copy: http://www.jmargolin.com/svr/refs/ref15_lunar_driving_history.pdf

Reference 16 - Evans & Sutherland Picture System:

Short Brochure: http://www.computerhistory.org/brochures/companies.php?alpha=d-f&company=com-42b9d8b7f4191

Full Brochure:
http://archive.computerhistory.org/resources/text/Evans_Sutherland/EvansSutherland.3D.1974.102646288.pdf

Mirrored copy:
Short Brochure: http://www.jmargolin.com/svr/refs/ref16_esps_s.pdf
Full Brochure: http://www.jmargolin.com/svr/refs/ref16_esps_f.pdf

Reference 17 – RC AeroChopper Review: http://www.atarimagazines.com/startv3n9/rcaerochopper.html

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref17_aerochopper.pdf

Reference 18 – Microsoft Flight Simulator

Microsoft Flight Simulator 5.1 Screen Shot:
http://www.jmargolin.com/svr/refs/ref18_fs5_1_screenshot.pdf
Microsoft Flight Simulator History: http://www.jmargolin.com/svr/refs/ref18_fs_history.pdf

Reference 19 – Microsoft Flight Simulator's first use of terrain points:
http://www.flightsim.com/cgi/kds?$=main/review/fs2000.htm

Mirrored copy: http://www.jmargolin.com/svr/refs/ref19_fs_first.pdf

Reference 20 – News releases from RTI (Research Triangle Institute), Avidyne, AvroTec, and NASA announcing NASA had selected those companies to develop a synthetic vision system for General Aviation. www.jmargolin.com/svr/refs/ref20_nasa1999.pdf

Reference 21: NASA press release, May 13, 1999, http://quest.nasa.gov/aero/news/05-13-99.txt

Mirrored copy: http://www.jmargolin.com/svr/refs/ref21_nasa_pr.pdf

Michael Braukus
Headquarters, Washington, DC
(Phone: 202/358-1979)
        May 13, 1999

Kathy Barnstorff
Langley Research Center, Hampton, VA
(Phone: 757/864-9886)

RELEASE: 99-59

SYNTHETIC VISION COULD HELP PILOTS STEER CLEAR OF FATALITIES

NASA and industry are developing revolutionary cockpit displays to give airplane crews clear views of their surroundings in bad weather and darkness, which could help prevent deadly aviation accidents.

Limited visibility is the greatest factor in most fatal aircraft accidents, said Michael Lewis, director of the Aviation Safety Program at NASA's Langley Research Center in Hampton, VA. NASA has selected six industry teams to create Synthetic Vision, a virtual-reality display system for cockpits, offering pilots an

electronic picture of what's outside their windows, no matter the weather or time of day.

"With Global Positioning Satellite signals, pilots now can know exactly where they are," said Lewis. "Add super-accurate terrain databases and graphical displays and we can draw three-dimensional moving scenes that will show pilots exactly what's outside. The type of accidents that happen in poor visibility just don't happen when pilots can see the terrain hazards ahead."

The NASA Aviation Safety Program envisions a system that would use new and existing technologies to incorporate data into displays in aircraft cockpits. The displays would show hazardous terrain, air traffic, landing and approach patterns, runway surfaces and other obstacles that could affect an aircraft's flight.

Industry teams submitted 27 proposals in four categories: commercial transports and business jets, general aviation aircraft, database development and enabling technologies. NASA and researchers from the Federal Aviation Administration and Department of Defense evaluated the proposals' technical merit, cost and feasibility.

NASA has committed $5.2 million that will be matched by $5.5 million in industry funds to advance Synthetic Vision projects over the next 18 months. More money is expected to be designated later to accelerate commercialization and make some systems available within four to six years.

Among the team leaders selected for the first phase of the program are: Rockwell Collins, Inc., Cedar Rapids, IA; AvroTec, Inc., Portland, OR; Research Triangle Institute, Research Triangle Park, NC; Jeppesen-Sanderson, Inc., Englewood, CO; the Avionics Engineering Center of Ohio University, Athens, OH; and Rannoch Corporation, Alexandria, VA.

Rockwell Collins, Inc. will receive funds to develop synthetic vision for airliners and business jets. The AvroTec, Inc. and Research Triangle Institute groups will use their awards to create technologies for a general-aviation synthetic vision system. A team led by Jeppesen-Sanderson, Inc. will receive funds to develop terrain database requirements and system approaches. The Avionics Engineering Center of Ohio University and Rannoch Corporation will use their awards to design specific component technologies for Synthetic Vision.

The Aviation Safety Program is a partnership with the FAA, aircraft manufacturers, airlines and the Department of Defense.

This partnership supports the national goal announced by President
Clinton to reduce the fatal aircraft accident rate by 80 percent
in 10 years and by 90 percent over 25 years.

Because of advances in the last 40 years, commercial
airliners are already the safest of all major forms of
transportation. But with an accident rate that has remained
relatively constant in the last decade and air traffic expected to
triple over the next 20 years, the U.S. government wants to
prevent a projected rise in the number of aircraft accidents.

For a complete list of industry teams please check the
Internet at:

http://oea.larc.nasa.gov/news_rels/1999/May99/99-025.html

- end -

Reference 22 – **Virtual Cockpit Window" for a Windowless Aerospacecraft,** NASA Tech Briefs.
January 2003, page 40. http://www.nasatech.com/Briefs/Jan03/MSC23096.html
Mirrored Copy: http://www.jmargolin.com/svr/refs/ref22_nasa_techbriefs.pdf

"Virtual Cockpit Window" for a Windowless Aerospacecraft

Wednesday, January 01 2003

A software system processes navigational and sensory information in real time to generate a
three- dimensional- appearing image of the external environment for viewing by crewmembers
of a windowless aerospacecraft. The design of the particular aerospacecraft (the X-38) is such
that the addition of a real transparent cockpit window to the airframe would have resulted in
unacceptably large increases in weight and cost.

When exerting manual control, an aircrew needs to see terrain, obstructions, and other features
around the aircraft in order to land safely. The X-38 is capable of automated landing, but even
when this capability is utilized, the crew still needs to view the external environment: From the
very beginning of the United States space program, crews have expressed profound dislike for
windowless vehicles. The well-being of an aircrew is considerably promoted by a three-
dimensional view of terrain and obstructions. The present software system was developed to
satisfy the need for such a view. In conjunction with a computer and display equipment that
weigh less than would a real transparent window, this software system thus provides a "virtual
cockpit window."

The key problem in the development of this software system was to create a realistic three-
dimensional perspective view that is updated in real time. The problem was solved by building
upon a pre-existing commercial program — LandForm C3 — that combines the speed of flight-
simulator software with the power of geographic-information-system software to generate real-
time, three-dimensional-appearing displays of terrain and other features of flight environments.
In the development of the present software, the pre-existing program was modified to enable it to
utilize real-time information on the position and attitude of the aerospacecraft to generate a view

of the external world as it would appear to a person looking out through a window in the aerospacecraft. The development included innovations in realistic horizon-limit modeling, three-dimensional stereographic display, and interfaces for utilization of data from inertial-navigation devices, Global Positioning System receivers, and laser rangefinders. Map and satellite imagery from the National Imagery and Mapping Agency can also be incorporated into displays.

After further development, the present software system and the associated display equipment would be capable of providing a data-enriched view: In addition to terrain and obstacles as they would be seen through a cockpit window, the view could include flight paths, landing zones, aircraft in the vicinity, and unobstructed views of portions of the terrain that might otherwise be hidden from view. Hence, the system could also contribute to safety of flight and landing at night or under conditions of poor visibility.

In recent tests, so precise was the software modeling that during the initial phases of the flight the software running on a monitor beside the video camera produced nearly identical views.

This work was done by Michael F. Abernathy of Rapid Imaging Software, Inc., for Johnson Space Center. For further information, please contact Michael F. Abernathy, Rapid Imaging Software, Inc., 1318 Ridgecrest Place S.E., Albuquerque, NM 87108. MSC-23096.

Reference 23 – Press Release from Rapid Imaging Software, Inc. (http://www.landform.com/pages/PressReleases.htm) which states (near the bottom of the page): Mirrored copy: http://www.jmargolin.com/svr/refs/ref23_ris.pdf

On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as "the best seat in the house", the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight.

Reference 24 – **Description of Path-in-the-Sky Contact Analog Piloting Display**, Charles E. Knox and John Leavitt, October 1977, NASA Technical Memorandum 74057 http://ntrs.nasa.gov/archive/nasa/casi.ntrs.nasa.gov/19780002119_1978002119.pdf

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref24_knox.pdf

Reference 25 - "The Electronic Terrain Map: A New Avionics Integrator", Small, D.M. USAF, Avionics Laboratory, Wright-Patterson AFB, OH, AIAA-1981-2289. In: Digital Avionics Systems Conference, 4th, St. Louis, MO, November 17-19, 1981, Collection of Technical Papers. (A82-13451 03-04) New York, American Institute of Aeronautics and Astronautics, 1981, p. 356-359.
http://www.jmargolin.com/svr/refs/ref25_small.pdf

Converted to text using OCR: http://www.jmargolin.com/svr/refs/ref25_small.html

Reference 26 - This is part of the Washington Sectional Aeronautical Chart, Scale 1:500,000 55th Edition, published March 3, 1994 by U.S. Department of Commerce National Oceanic and Atmospheric Administration National Ocean Service.

Map: http://www.jmargolin.com/svr/refs/ref26_pmap1.pdf
Washington Legend showing paper map symbology: http://www.jmargolin.com/svr/refs/ref26_pmap2.pdf

Reference 27 - Using Synthetic Images to Register Real Images with Surface Models; Horn, Berthold K.P.; Bachman, Brett L. ; August 1977.

MIT DSpace: http://hdl.handle.net/1721.1/5761

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref27_horn.pdf

> Abstract: A number of image analysis tasks can benefit from registration of the image with a model of the surface being imaged. Automatic navigation using visible light or radar images requires exact alignment of such images with digital terrain models. In addition, automatic classification of terrain, using satellite imagery, requires such alignment to deal correctly with the effects of varying sun angle and surface slope. Even inspection techniques for certain industrial parts may be improved by this means.

Reference 28 - U.S. Patent 3,328,795 **Fixtaking Means and Method** issued June 27, 1967 to Hallmark.

USPTO Database (Does not have htmp version): http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=3,328,795.PN.&OS=PN/3,328,795&RS=PN/3,328,795

PDF Version: http://www.jmargolin.com/svr/refs/ref28_3328795.pdf

Reference 29 – U.S. Patent 4,347,511 **Precision navigation apparatus** issued August 31, 1982 to **Hofmann, et al.**

From USPTO: http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=4,347,511.PN.&OS=PN/4,347,511&RS=PN/4,347,511

PDF Version: http://www.jmargolin.com/svr/refs/ref29_4347511.pdf

Reference 30 – I don't know if Terrain Referenced Navigation works over Kansas, but I know Kansas is flat. From: http://www.guardian.co.uk/education/2003/sep/25/research.highereducation2

This year, for instance, three geographers compared the flatness of Kansas to the flatness of a pancake. They used topographic data from a digital scale model prepared by the US Geological Survey, and they purchased a pancake from the International House of Pancakes. If perfect flatness were a value of 1.00, they reported, the calculated flatness of a pancake would be 0.957 "which is pretty flat, but far from perfectly flat". Kansas's flatness however turned out to be 0.997, which they said might be described, mathematically, as "damn flat".

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref30_kansas.pdf

Reference 31 - U.S. Patent 4,660,157 **Real time video perspective digital map display method** issued April 21, 1987 to Beckwith, et al.

USPTO (html): http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=4,660,157.PN.&OS=PN/4,660,157&RS=PN/4,660,157

PDF: http://www.jmargolin.com/svr/refs/ref31_4660157.pdf

Reference 32 – U.S. Patent 5,179,638 **Method and apparatus for generating a texture mapped perspective view** issued January 12, 1993 to Dawson, et al.

USPTO (html): http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=5,179,638.PN.&OS=PN/5,179,638&RS=PN/5,179,638

PDF: http://www.jmargolin.com/svr/refs/ref32_5179638.pdf

Reference 33 - U.S. Patent 4,884,220 **Address Generation with Variable Scan Patterns** issued November 28, 1989 to Dawson et al.

USPTO (html): http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=4,884,220.PN.&OS=PN/4,884,220&RS=PN/4,884,220

PDF: http://www.jmargolin.com/svr/refs/ref33_4884220.pdf

Reference 34 - **VCASS: An Approach to Visual Simulation**, Kocian, D., 1977, Presented at the IMAGE Conference, Phoenix, Ariz., 17-18 May 77.

Available for purchase from DTIC http://www.dtic.mil/srch/doc?collection=t2&id=ADA039999
Mirrored Copy: http://www.jmargolin.com/svr/refs/ref34_vcass.pdf

Converted to text using OCR (with the paragraphs numbered):
http://www.jmargolin.com/svr/refs/ref34_vcass.htm

Reference 35 – The earliest known description of the invention that became U.S. Patent 5,566,073 **Pilot Aid Using A Synthetic Environment.** http://www.jmargolin.com/svr/refs/ref35_pilotdoc.pdf

Reference 36 - U.S. Patent 5,566,073 **Pilot Aid Using A Synthetic Environment** issued October 15, 1996 to Margolin

USPTO (html): http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=5,566,073.PN.&OS=PN/5,566,073&RS=PN/5,566,073

PDF: http://www.jmargolin.com/svr/refs/ref36_5566073.pdf

Reference 37 – U.S. Patent 5,904,724 **Method and apparatus for remotely piloting an aircraft** issued May 18, 1999 to Margolin

USPTO (html): http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=5,904,724.PN.&OS=PN/5,904,724&RS=PN/5,904,724

PDF: http://www.jmargolin.com/svr/refs/ref37_5904724.pdf

Reference 38 - U.S. Patent Application Publication 20080033604 **System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace**

USPTO (html): http://appft1.uspto.gov/netacgi/nph-Parser?Sect1=PTO2&Sect2=HITOFF&u=%2Fnetahtml%2FPTO%2Fsearch-adv.html&r=18&p=1&f=G&l=50&d=PG01&S1=%22synthetic+vision%22&OS=%22synthetic+vision%22&RS=%22synthetic+vision%22

PDF: http://www.jmargolin.com/svr/refs/ref38_pg3604.pdf

Reference 39 – Letter sent to Optima Technology Group by Rapid Imaging Software attorney Benjamin Allison, dated October 13, 2006. http://www.jmargolin.com/svr/refs/ref39_ris.pdf

Reference 40 - NTSB Incident Report on crash of Predator on April 25, 2006, northwest of Nogales, NM. NTSB Identification **CHI06MA121**

http://www.ntsb.gov/ntsb/brief.asp?ev_id=20060509X00531&key=%201

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref40_ntsb.pdf

.end

1996 Annual Report

Automation, Robotics, & Simulation Division

00955

Portable Diagnostic Terminal Software for the X-38
Francisco J. Delgado

The Portable Diagnostic Terminal (PDT) is an IBM Thinkpad that can be carried about and connected to the onboard X-38 flight computer via an ethernet TCP/IP connection. The PDT serves as the interface to all X-38 subsystems. On the ground before the vehicle is launched the PDT provides the capability to checkout the health and status of the vehicle subsystems and perform software loads. While docked with the Space Station the PDT will be used to conduct routine subsystem health monitoring and to perform software loads. When the X-38 lands, the PDT will be used to download data from the flight recorder and perform immediate vehicle checkout. During test phases the PDT will be used to perform initialization loads for the flight computer, flight performance data monitoring, system activation, and vehicle test and checkout.

The PDT will be used to upload/download: flight software, flight software initialization data files (I-loads), and recorded flight data. It will also perform flight system sequence execution and monitoring for system activation sequences, system deactivation sequences, and test sequences. Further more it will also provide flight test operator support of the test vehicle for ground flight data display and recording, system commanding, and vehicle release go/no-go decision support.

During 1996, requirements were collected from all the different subsystems. These requirements were used to create the different subsystem displays, produce a PDT requirements document, and produce a PDT testing/operational procedures document. The PDT software written has been used to support a wide assortment of tests conducted, some of which include: two KC-135 X-38 test flight experiments, an early Electro-Mechanical Actuator testbed experiment, INS/GPS testbed experiments, and early 131 X-38 test vehicle integration. All the PDT software created was written under the LabView 3.1 environment. Figure 1.0 depicts the object oriented approached selected for the PDT software architecture. Along with the individual subsystem displays, a summary screen has been developed that gives the user a summarized description of the health and launch commit criteria status for all the different subsystems. Subsystems monitoring and commanding displays have been developed for: Parachute and Pyrotechnics, INS/GPS, Communication & Tracking, Flight Safety, Power and Distribution, Flush Air Data System, and Fire Suppression. Along with these subsystems, additional displays have been built to accommodate for unit testing of different hardware components, test boxes, and PDT to flight computer remote commanding.

Future plans are to continue development of the PDT software. This continued development includes: adding any additional subsystem displays necessary, adding PDT resident FDIR software, and modifying the current displays on an as needed basis.

Initialize
Sets any parameters to the required starting values/states.

Show
Loads the display panels so that viewing of the different displays is possible

Commanding
Scan to see if any remote commands need to be sent to the flight computer from the PDT.

1 Initialize Displays and Open TCP/IP Connection

2 Select a display to view
Update displays, look for remote commands, check for Health, and check RFF of Subsystems

Executive

3 Terminate Displays and Close TCP/IP Connection

Run-Time Loop

Update
Loads new values to the appropriate indicators and graphs.

Health
Perform the neccessary calculations required to assess the health of the different subsystems

RFF
Perform the neccessary commit for launch criterea checks for the different subsystems

Terminate
Sets any parameters to the required termination values/states and closes all the display panels for the different subsystems.

Figure 1.0: This figure illustrates the object oriented approach selected as the software architecture for the PDT. Each subsystem display, 18 in all to this point, has seven different methods associated with it. These methods are: Initialize, Show, Update, Commanding, RFF, Health, and Terminate. The executive calls each method of each display in the sequential order depicted above.

00957

Advanced Algorithms for the X-38 Flush Air Data System
Francisco J. Delgado

Increasingly, flight systems designs for advanced aerospace vehicles are requiring the availability of accurate and high-fidelity air data; such as, angle of attack (alpha) and side slip angle (beta), see figure 1.0. As a means of circumventing many difficulties associated with conventional air data system, a flush air data sensing system (FADS) concept was originated at NASA Langley Research Center and flight tested at the NASA Dryden Flight Research Facility (DFRF). This FADS has been chosen for use on the X-38 vehicle to calculate the air data parameters used during flight.

The X-38 FADS system is depicted in figure 2.0. It consists of a total of nine pressure sensors arranged in a crucifix fashion on the nose-cone of the vehicle. The current software that calculates the required air data parameters uses an analytical algorithm, referred to a TRIPLES. TRIPLES takes every possible subset of three pressure sensors on the vertical axis and using non-linear regression algorithms calculates alpha for the vehicle. It then takes alpha and every possible combination of three pressure sensor readings on the horizontal axis and using more non-linear regression techniques, calculates beta. The current X-38 flight computer is a Motorola 68040 running on a 40 milli-second clock cycle. The FADS system is part of the data conversion/FDIR (SOP) which is allocated 3.5 ms. Of this 3.5 ms, the FADS system can use 2.0 ms to perform any required calculations. TRIPLES is currently taking about 11 ms to perform the required calculation, which is too slow. The FADS system does not include any FDIR to detect if any of the pressure sensors have failed.

Different neural network, fuzzy logic, signal processing, and statistical techniques are being investigated in an attempt to create and implement a fast, efficient, and accurate pattern recognition and function approximation system for the X-38 FADS. Wind tunnel data collected from a Texas A&M wind tunnel experiment for an X-38 model, in conjunction with abductive information modeling techniques have been used to develop polynomial functions which can quickly and effectively calculate alpha and beta given the nine pressure readings from the FADS pressure sensors. The abductive information modeling technology being investigated creates polynomial approximators in a supervised fashion, given a set of inputs and desired outputs it creates polynomials that map the inputs to the outputs. The wind tunnel data was randomly split into a training set, using 70% of the data, and a test set, using the remaining 30% of the data. Polynomials were created that can predict alpha and beta to within ± 1/2 degree. The polynomials created to calculate alpha and beta are simple, see figure 3.0. The polynomial used to calculate alpha takes approximately 6 micro-seconds to run, while the polynomial that calculates beta takes approximately 8 micro-seconds to run. Some redundancy management is being investigated to assure that the results obtained are a function of pressure sensors which have not failed. Figure 4.0 illustrates the total error associated with the polynomial functions created to predict alpha and beta. The error achieved is within ± 1/2 degree accuracy and performs all the required calculations well within the required 2 ms of CPU time.

Work is in progress to automatically detect and exclude any failed pressure sensor in any air data calculation, reducing the error from 1/2 to 1/3 degree accuracy, and providing

greater redundancy in the alpha and beta calculations. Everything is proceeding on schedule and all indications are that a fast, accurate, and robust computer algorithm can be developed for the X-38 FADS using the advanced technologies being investigated.


Figure 1.0: Depiction of the angle of attack (alpha), and the side slip angle (beta)

FADS nose ports looking aft

FADS ports looking at a side snapshot

Figure 2.0

$\alpha =$ -113.6619094394546163 -
0.1061964997847570983 * $(port_{1,0})$ +
0.23227296933655534870 * $(port_{1,1})$ +
0.52033467222133431026 * $(port_{2,2})$ -
0.69355540584819347475 * $(port_{3,3})$ -
0.06176579284750127228 * $(port_{4,4})$ -
0.31728533305747604264 * $(port_{5,5})$ -
0.37921397684197324I4 * $(port_{6,6})$ +
0.40676968170923367I8 * $(port_{7,7})$ +
0.45740063887770753I9 * $(port_{8,8})$

$\beta =$ 13484.87438897148928 +
62.10266139990333956000000 * $(port_{2,1})$ -
0.028990601479148646980000 * $(port_{1,1})^2$ +
0.000004538523173669934163 * $(port_{2,1})^3$ -
81.80595775441593663000000 * $(port_{2,1})$ +
0.038592090250964505440000 * $(port_{2,1})^2$ -
0.000006098804663683331946 * $(port_{2,1})^3$

Figure 3.0: Simple polynomials created to predict alpha and beta, using the 9 pressure port sensor readings

Figure 4.0: Absolute error (in degrees) for the polynomials used to predict alpha and beta.

00959

FY97
Annual
Report

Automation, Robotics,
& Simulation Division

Accurate Determination of Flight Control Air Data Parameters Using Artificial Neural Networks and the X-38 Flush Air Data System
Frank Delgado

The X-38 program is developing a series of prototype flight test vehicles leading to a functional Crew Return Vehicle (CRV). The development of these prototype vehicles will demonstrate which technologies are needed to build an inexpensive, safe, and reliable spacecraft that can rapidly return astronauts from onboard the International Space Station (ISS) to Earth. These vehicles are being built using an incremental approach and where appropriate, are taking advantage of advanced technologies that may help improve safety, decrease development costs, reduce development time, and outperform traditional technologies. The operational CRV will be fully automated and require very little crew interaction during its return trip to Earth.

A Flush Airdata System (FADS), originally developed at the NASA Langley Research Center and flight tested at the NASA Dryden Flight Research Facility (DFRF), is being used on the X-38 program to provide airdata parameters required for an automated flight control system. The X-38 FADS uses a matrix of 9 pressure ports arranged in a crucifix pattern around the nose of the vehicle, figure 1.0. The differences between the pressure values at the different port locations can be used to determine: the angle of attack (α), angle-of-sideslip (β), Mach number (M), and free stream static pressure (P_{∞}), figure 2.0. The determination of other airdata parameters can be computed from these parameters using standard aerodynamic equations. The software used at the DFRF with this FADS is called TRIPLES. The slow execution of the TRIPLES software on the X-38 flight computer, a Motarola 68040 running in a 40 ms clock cycle, raised concerns and initiated an investigation into the use of Neural Network (NN) technology as a possible replacement for TRIPLES.

Wind tunnel data collected at different α, β, M, and P_{∞} for a 5.2-percent scaled version of the X-38 vehicle was used to create different Neural Networks that can quickly and accurately determine the required flight control airdata parameters, given the 9 pressure port readings on the nose of the vehicle. The NN paradigm selected is called abductive information modeling and is implemented in a software package called ModelQuest Enterprise, which was developed by Abtech corporation under a NASA phase II Small Business Innovative Research program grant. Additional training and testing data was collected during four X-38 captive carry tests.

The desired accuracy for the different airdata parameters are: +- 0.50° for α and β, +-0.03 for Mach, and +-50 psf for P_{∞}. The parameters must all be calculated within an extremely constrained computing environment. The FADS systems is allocated 2.0 ms of CPU time to perform all its required calculations. The TRIPLES algorithm is currently taking about 4.5 ms to run, while the NN can calculate the same parameters in ~0.90 ms. The NN achieved an average error of less than: +-0.11° for α and β, +-0.006 for M, and +-8.3 psf for P_{∞}, figure 3.0.

Work is in progress to automatically detect and exclude any failed pressure sensor in all air data calculations. The actual FADS system, TRIPLES or NN, that will used during active flight control will be selected early 1998. Everything is proceeding on schedule and the NN system developed so far has exceeded our initial expectations.

(a) FADS nose ports looking aft toward the nose

(b) FADS ports looking at a side snapshot of the vehicle

Figure 1.0

(a) Alpha is the angle that the XY plane makes with the velocity vector

(b) Beta is the angle that the XZ plane makes with the velocity vector

Figure 2.0

Figure 3.0: Error plots for α, β, M, and P_{inf} Using the Lockheed Martin Vought Systems Windtunnel Data

Portable Diagnostic Terminal Software for the X-38
Frank Delgado

The Portable Diagnostic Terminal (PDT) is an IBM Thinkpad that can be carried about and connected to the onboard X-38 flight computer via an ethernet Transmission Control Protocol/Internet Protocol (TCP/IP) connection. The PDT serves as the interface to all the X-38 subsystems. On the ground before the vehicle is launched the PDT provides the capability to checkout the health and status of the vehicle subsystems and perform software loads. During captive carry tests, when the vehicle is attached to the B52 (figure 1.0), the PDT will be used to conduct routine subsystem health monitoring, and mode the vehicle into a free flight mode. When the X-38 lands, the PDT will be used to download data from the flight recorder, perform immediate vehicle checkout, and begin post flight shutdown procedures. During non-flight tests the PDT will be used to perform initialization loads for the flight computer, flight performance data monitoring, system activation, and vehicle test and checkout.

The PDT will be used to upload/download: flight software, flight software initialization data files (I-loads), and recorded flight data. It will also perform flight system sequence execution and monitoring for system activation sequences, system deactivation sequences, and test sequences. Furthermore, it will provide flight test operator support of the test vehicle for ground flight data display and recording, system commanding, and vehicle release go/no-go decision support.

During 1997, additional requirements, above and beyond those collected in 1996, were collected from different subsystems and incorporated into the PDT testing/operational procedures document. These new requirements were also implemented into the operational PDT code. The PDT was used to support several KC135 flights, and 4 captive carry tests. All the PDT software was written under the LabView 4.0.1 environment. Figure 2.0 depicts the object oriented approached selected for the PDT software architecture. Along with the individual subsystem displays, a summary screen was developed that gives the user a summarized description of the health and launch commit criteria status for all the different subsystems. Subsystems monitoring and commanding display support was provided for: Parachute and Pyrotechnics, Inertial Navigation System/Global Positioning System (INS/GPS), Communication and Tracking, Flight Safety, Power and Distribution, Flush Air Data System, and Fire Suppression. Along with these subsystems, additional displays have been built to accommodate for unit testing of different hardware components, test boxes, and PDT to flight computer remote commanding.

A fully functional PDT has been developed, tested, and delivered to the X-38 program. Routine maintenance of the PDT has been handed over to Avionic Systems Division personnel and the Automation, Robotics, and Simulation Division's only involvement is in a consulting role.

Figure 1.0: Photograph of X-38 during captive carry flight 1. The X38 vehicle is attached to the wing of the B52 and flown around at different altitudes and velocities to collect data. To date four captive carry flights have been performed.


Figure 2.0: This figure illustrates the object oriented approach selected for the PDT software architecture. Each subsystem display has seven different methods associated with it: Initialize, Show, Commanding, Update, Ready for Flight (RFF), Health, and Terminate. The Executive begins by initializing every subsystem display, system level routines, and data warehouses. It then proceeds to the run-time loop, during which it brings in data, calibrates it, and calls the appropriate methods for each of the subsystem displays. The Executive remains in the run-time loop until one wishes to exit, at which time a couple of buttons are pressed on the screen and the executive calls the terminate method of each display and exits to a higher level starting screen.

00964

The Automation & Human Interface Computer for the X-38
Frank Delgado

The X-38 program was started in early 1995 to explore the feasibility of building a space station Crew Return Vehicle (CRV). The X-38 program is developing a series of test vehicles to demonstrate the low-cost technologies and methods required to developed a fully functional CRV. The X-38 program will use gradual buildup approach. It will start with a series of atmospheric and ground-based tests vehicles, known as: vehicle 131 (V131), vehicle 132 (V132), and vehicle 133 (V133), and culminate with the development of a space-capable test vehicle called vehicle 201 (V201). V201 be flown on the space shuttle as a payload experiment in 2001.

The Automation and Human Interface Computer (AHIC) will provide a graphical user interface that will provide astronauts, launch panel operators, and subsystem leads with the necessary feedback to quickly and accurately determine the health of the vehicle and its subsystems. AHIC will also include advanced Fault Detection Isolation and Recovery (FDIR) software and a mechanisms for operators to change the state of certain onboard devices using remote commands. Additionally AHIC will also include a documentation archive where one can access an assortment of document which may include: flight rules, flight procedure, diagrams, subsystem requirements, cue cards, etc.

Figure 1.0 illustrates the V133 and V201 AHIC architecture. The data comes into our system via the computer interface (RS422) and placed into the Data Collection & Calibration Module. The calibrated data is then passed to the Data Distribution and Inter-Module Communication (DDIMC), which acts as our architecture's nervous system and distributes the data to all the modules requiring the data. DDIMC also handles any inter-module communication that may be necessary.

For the graphical user interface on V133, we will focus on developing a virtual cockpit for the parachute system. We have acquired a 3 dimensional model of the X-38 and are currently collecting United States Geological Survey data at different altitudes. This terrain data will give us a realistic 3 dimensional terrain map of the region we will be flying over. We are also using a variety of virtual reality modeling tools to build objects which will be used in the virtual cockpit. We will take all of this and tie it together using Template Graphics 3D Mastersuite to build a virtual cockpit that will give the visual affect of what it would look like, from the vehicle, from the post parachute deploy phase to the actual landing of the vehicle. The cockpit will have the ability to uplink commands to the vehicle, using a UHF system, which will give it the ability to steer the parachute. This cockpit could be used to control the parachute from any remote location, whether its out in the desert, in hanger or where ever one may be. For V201 we will take all the information we have learned from our V133 endeavor, all the information that Steve Harris (human factors person) can provide, and all the information that's coming from the weekly human interface meetings to help us begin developing the human interface software for V201.

The monitoring modules (inter-system and subsystem) will provide fault detection, isolation, and recovery procedure for subsystem and vehicle level systems. The inter-system module will detect inter-system failures, which is very difficult for individual subsystems to detect because subsystems typically do not have the required insight into other subsystems. Both modules will prioritize failures based on: flight phase, procedure being performed, or the current state of the system.

The situation assessment module will behave as a data retrieval agent who's job is to go out and gather as much information as possible about a specific situation. Let's say we are flying around and some sort of anomaly is detected. This module's task is to go out and collect all the information that may be required to aid the operators in determining what caused the anomaly. The information it retrieves may be parameters, schematics, procedures, or any other information it believes is relevant.

The documentation archive will be a document warehouse where electronically formatted documents can be stored. Some examples of the types of documents that may be stored are: schematics, flight rules, flight procedures, cue cards, etc. We will have a special interface into this archive that will allow easy hyper-linked access to the documents stored. This interface will work like the help wizards found in many of today's applications.

The next three modules are closely inter-related and may actually be combined into one element as we finalized the architecture. The remote command module will allow the operator to send individual commands to the flight computer, much like the X-38 Portable Diagnostics Terminal does today. It will perform some minor checks to assure that command was received and understood by the flight computer. Automated sequencing will allow a pre-determined set of commands to be sent to the flight computer. This module can be placed in one of two modes: automatic or manual. In automatic mode the commands would be automatically sent to the flight computer one after the other. In manual mode, the user would tell the system it wants to manually execute a specific procedure, at which point the system would pull up the required commands and place them on the screen. The user would have to manually arm and fire each of the commands individually. The Procedure tracking module monitors the sequencing activities occurring and makes sure that the procedures being executed are causing the right actions to take place.

The hardware selected for the 133 vehicle will consist of two Computer Dynamics™ flat panel computers. These computer are 200 MHZ Pentium machines with MMX, 64 megabytes of RAM, and a 1 gigabyte hard drive. The dimensions of the entire unit (CPU + flat panel display) is 16" x 11.7" x 3.5". The hardware for vehicle 201 is TBD. Our code development will be done using C++ in a Windows NT environment. We will also be using Template Graphics 3D Mastersuite.

An evaluation into the different 3D terrain modeling tools, flight planning software ,and virtual reality modeling tools is being performed. The basic AHIC architecture for the V133 and V201 is being finalized and the development of the serial interface between the flight computer and the AHIC is currently being written. Everything is proceeding on schedule and no major problems are expected.

00366

□ Targeted for Vehicle 133 Development

Figure 1.0: Automation and Human Interface Computer Architecture for vehicles 133 and 201. The shaded modules (boxes) will be the modules developed for vehicle 133.

The Application of a Polynomial Network in Failure Detection, Isolation, and Recovery (FDIR) of the Flush Air Data System (FADS) for the X-38 Spacecraft

James Carvajal and Frank Delgado

The following figure represents the process used by the X-38 Flush Air Data System (FADS) software to determine when a pressure measurement is not reasonable based upon previously calculated aerodynamic parameters. For this figure, α is the angle of attack, β is the angle of sideslip, M is the mach number, $\bar{q}$ is the dynamic pressure, and P_∞ is the ambient pressure.

Figure 1: The Failure Detection, Isolation, and Recovery Scheme

The most significant consequence of this approach is how to develop the appropriate mapping functions, labeled f_i's, which can sufficiently approximate the actual system dynamics so that failing sensors are properly rejected, while simultaneously ensuring that the noise encountered in the flight does not cause good sensor measurements to be considered failed. For the current X-38 prototype, there are nine high pressure ports (rated at plus or minus five psi), and the operating range for α is between minus 20 to 50 degrees, β between plus and minus five degrees, and mach between 0.1 and 0.95. Figure 2 provides an example of the data mapping that must be captured for a single port, in this case the second one, at a selected angle of sideslip of 5 degrees. Given the considerable volume of data required to be mapped and the strict real-time performance constraints available in the X-38's flight computer, nine separate Polynomial Networks were developed to model the total system. The final plot, Figure 3, provides a graph of the differences between the measured pressure value and the output of

the trained Polynomial Network for the second pressure port as measured in the first captive carry flight.

Pressure Port 2 for Beta = 5

Figure 2: Example of Pressure Coefficients for the Second Pressure Port

Figure 3: Flight Results from First Captive Carry Flight

Flight Results from the X-38 Flush Air Data System Software
James Carvajal and Frank Delgado

The technology developments required for an advanced spacecraft, such as the X-38, can be an overwhelming task unless it is carefully merged together in a controlled process. The approach chosen for the X-38 was to develop a series of test vehicles, each of which is progressively more advanced and refined. The first flight test vehicle, designated Vehicle 131 was designed and built here at the JSC, and was shipped to the Dryden Flight Research Center (DFRC) last June. Vehicle 131 has a flight control system for the parafoil, but does not have any active control surfaces. As conventional air data probes would not be able to survive the heat of a reentry, a Flush Air Data System (FADS) was selected to be one of the critical systems to demonstrate early in the program using Vehicle 131.

On July 24, Vehicle 131 was attached to the B-52 pylon and the first taxi test was accomplished. Figure 1 presents a picture of how Vehicle 131 was attached to the carrier aircraft. The first captive carry flight test was then completed on July 30. Figure 2 shows some flight results from this flight, both for the new "Triples Algorithm" developed by DFRC, and, for an alternative technique based upon neural and statistical networks known as a Polynomial Networks. Note that both solutions compare favorably with the results from the original X24a manned vehicle.

Three other captive carry test were also successfully completed in 1997. This allowed for additional data to be gathered in other flight regimes for the evaluation of the performance of the FADS system. Extra flight objectives included the validation of avionics systems in flight environments, clearance of the flight envelope, and end-to-end communications.

Figure 1: Vehicle 131 under the wing of the Boeing B-52.

Figure 2: The Results from the Flush Air Data System for the First Captive Carry Flight

Triples Alpha vs. NN Alpha

Triples Beta vs. NN Beta

Actual vs. NN Static Pressure

Actual Mach vs. NN Mach

AUTOMATION ROBOTICS AND SIMULATION DIVISION

NASA-JSC

1998 ANNUAL REPORT

Portable Diagnostic Terminal Software for the X-38
Frank Delgado

The X-38 program was started in early 1995 to explore the feasibility of building a space station Crew Return Vehicle (CRV). The X-38 program is developing a series of test vehicles to demonstrate the low-cost technologies and methods required to develop a fully functional CRV that can rapidly return astronauts from onboard the International Space Station (ISS) to earth. The X-38 program will use a gradual buildup approach, building a series of atmospheric and ground-based tests vehicles. There will be three atmospheric test vehicles and one space rated vehicle developed and tested during the X-38 program. The vehicles are known as vehicle 131 (V131), vehicle 132 (V132), vehicle 133 (V133), and vehicle 201 (V201). V201 is space-rated and will fly on the shuttle as a payload bay experiment in November 2000.

The Portable Diagnostic Terminal (PDT) is an IBM ThinkPad that can be carried about and connected directly into the X-38 prototypes' patch panel. The PDT uses the Transmission Control Protocol/Internet Protocol (TCP/IP) to talk to the onboard flight computer. It's our one way of communicating with the onboard flight computer and determining what's going on before releasing the vehicle. On the ground before the vehicle is launched, the PDT provides the capability to checkout the health and status of the vehicle subsystems and perform software loads. During captive carry tests, see figure 1.0, the PDT is used to conduct subsystem health monitoring, and prepare the vehicle for free flight mode. When the X-38 lands, the PDT is used to download data from the flight recorder, perform vehicle checkout, and begin post flight shutdown procedures. During non-flight tests, the PDT is used to perform initialization loads for the flight computer, flight performance data monitoring, system activation, and vehicle test and checkout. The PDT is also used for software/hardware testing on several of the X-38 testbeds, including: the avionics testbed, the simulation testbed, and the guidance, navigation, and control testbed.

For V131, additional requirements, above and beyond those collected in 1997, were defined and incorporated into the V131 PDT load. This load was used to support 7 captive carry flights and one free flight, see figure 2.0. The load was also used to support KC135 testing, and the X-38 mobile test simulator. In addition to the V131 PDT load, a new PDT version was developed to support the buildup, testing, and delivery of V132.

The PDT software was written under the LabView 4.0.1 environment using an object-oriented approach. Along with the individual subsystem displays, a summary screen was developed that gives the user a summarized description of the health and launch commit criteria status for all the different subsystems. Subsystems monitoring and commanding display support was provided for the: Parafoil System, GNC System, Electrical Mechanical Actuator System (EMA), Pyrotechnic System, Inertial Navigation System/Global Positioning System (INS/GPS), Communication and Tracking System, Flight Safety, Power and Distribution System, Flush Air Data System, and the Fire Suppression System. Along with these subsystems, additional displays have been built to accommodate for unit testing of different hardware components, test boxes, and PDT to flight computer remote commanding.

Plans for this coming year include the use of both V131 and V132 PDT loads to: support upcoming captive carries and free flights for both vehicles, support testbed activities, and support the mobile cockpit.

Figure 1- Photograph of X-38 V131 during captive carry flight 1. The X38 vehicle is attached to the wing of the B52 and flown around at different altitudes and velocities to collect data. To date seven captive carry flights have been performed.


Figure 2 - Photograph of X-38 V131 during free flight 1. The vehicle is released from the wing of the B-52, after several seconds of "free flight," a parafoil system is deployed and is used to land the vehicle.

Immersive Situation Awareness for the X-38 Program
Frank Delgado

The NASA Johnson Space Center is developing a series of prototype flight test vehicles leading to a functional Crew Return Vehicle (CRV). The development of these prototype vehicles, designated as the X-38 program, will demonstrate which technologies are needed to build an inexpensive, safe, and reliable spacecraft that can rapidly return astronauts from onboard the International Space Station (ISS) to earth. These vehicles are being built using an incremental approach and where appropriate, are taking advantage of advanced technologies that may help improve safety, decrease development costs, reduce development time, and outperform traditional technologies.

The X-38 vehicles are unique in that they do not afford crew members a forward view through a wind screen. As a result, we have begun developing an application, based on Rapid Imaging Systems latest technology, that creates a computer generated immersive environment to provide the necessary information concerning the vehicles position, attitude, and status of the vehicle. The immersive environment consists of a set of 3-D displays that can be used for flight guidance and situation awareness. These displays feature the incorporation of real-time INS/GPS data for position and attitude, three dimensional terrain models, Heads-Up Display (HUD), ideal and actual glide path, recommended landing areas, vehicle in the scene, as well as typical system monitoring information. Maps, such as aeronautical charts, as well as satellite imagery are optionally overlayed on the 3-D terrain model to provide additional situation awareness, see figure 1.0. The HUD indicators created have been based upon both military aircraft HUD standards (MIL-STD-1787B) and Space Shuttle HUD standards (STS83-0020V2-26B).

During this year a sophisticated HUD was created and tested that included various two-dimensional and three-dimensional display indicators. The developed application was evaluated by X-38 engineers, human factors engineers, and astronauts. We have used the application developed, in unison with a European Space Agency (ESA) provided X-38 parafoil simulator, to allow engineers & crew members to simulate a person-in-the-loop X-38 parafoil landing. The application has proven very useful helping define what information is required to manually fly the X-38 during parafoil flight. We have also used the application for data analysis by playing back captive carry and free flight data from previous flights, see figure 2.0. Additionally we have incorporated the application into the X-38 mobile cockpit simulator.

Some of the questions that we will answer this coming year are: is the frame update rate sufficient to support realistic situational awareness, do the displays present adequate information density throughout the flight, and are the display modes useful in this environment. We will also integrate this application in the monitoring and control stations that will be used to remotely pilot the X-38 vehicles during parafoil flight. Additionally, we will continue a process of feedback and development, which will support crew members and X-38 engineers requirements for utility in HUD overlays and modes of operation during all flight phases of the X-38 vehicles.

a) In the out-the-window section we see a virtual "out a window view" with HUD symbology superimposed. In the GODS eye-view section, we can see an aeronautical chart.

b) This display incorporates the use of high-resolution satellite imagery. In the out-the-window section, we see a virtual environment that includes the vehicle in the scene along with typical HUD symbology. In the GODS eye-view section we see an overhead view of the area we are flying.

Figure 1 -   These are typical situation awareness displays. The displays are created in a window that is divided into 2 sections: an out-the-window section and a birds eye-view section.

Enhanced and Synthetic Vision 1999

Jacques G. Verly
Chair/Editor

00979

the occasions when this assumption is violated, as for example on crossing a coast, the model's constraint curve is the wrong shape but the parameter fitting strategy maintains acceptably (but not optimally) enhanced output imagery.

It has not been possible to make a full study and analysis of the noise processes in the video system; this is essential if the model fitting technique using overflow and underflow population distributions is to be optimized. For simplicity, a zero-mean, additive Gaussian noise model has been used in the demonstrator. A more detailed understanding of ground-truth statistics would also be of benefit since the underlying objective is to produce an image with these same statistics.

Despite these practical difficulties, the technology demonstrator has shown some very impressive results. We view the identification of its shortcomings as an important positive step towards specifying a prototype system, which we believe, is now a practical proposition.

5. CONCLUSIONS

A parallel signal processing computer was built and programmed to demonstrate that a method, previously reported by Oakley, of enhancing the contrast of hazy images from an airborne camera could be speeded up by between four and five orders of magnitude and made to work in real-time. The demonstration computer was constructed from off-the-shelf commercial modules, installed on the expansion bus of an ordinary PC, and programmed in C. A systematic study identified a combination of data pipelining techniques and algorithmic simplifications that allowed us to increase throughput by a factor of between ten thousand and one hundred thousand times. None of these simplifications to the underlying geometric and contrast-loss models perceptibly degrades the appearance of the enhanced imagery, which remains restricted by physical phenomena such as noise from various sources. The demonstrator has performed impressively well on recorded test data even in the presence of calibration and synchronization errors, and we are confident that even better results would be obtained with live data. The feasibility of implementing a real-time contrast enhancement method based on an atmospheric scattering model using readily available computer equipment has been amply demonstrated.

ACKNOWLEDGEMENTS

REFERENCES

1 J. P. Oakley, B. L. Satherley, C. G. Harrison and C. S. Xydeas, "Enhancement of image sequences from a forward-looking airborne camera", *Proceedings of the SPIE (IV) – Image and Video Processing*, 2666, pp. 266-276, 1996.

2 J. P. Oakley and B. L. Satherley, "Improving Image Quality in Poor Visibility Conditions Using a Physical Model for Contrast Degradation", *IEEE Transactions on Image Processing*, 1997.

3 J. P. Oakley, "Enhancement of Aerial Images", *UK Patent 9514834/2*.

4 J. Klek, "Real-time implementation of an aerial image enhancement algorithm", *M.Phil thesis*, University of Manchester, 1997.

5 P. Bazarnik, "Real-time implementation of a motion compensation algorithm", *M.Phil thesis*, University of Manchester, 1996.

6 R. V. Klassen, "Modeling of the effect of the atmosphere on light", *ACM Transactions on Graphics*, 6 (3), 1987.

7 P. J. Willis, "Visual simulation of atmospheric haze", *Computer Graphics Forum*, 6 pp.35-42, North-Holland, 1987.

8 Sundance Multiprocessor Technology Ltd., 4 Market Square, Amersham, Buckinghamshire, HP7 0DQ, UK.

9 Transtech Parallel Systems Ltd., 17-19 Manor Court Yard, Hughenden Avenue, High Wycombe, Buckinghamshire, HP13 5RE, UK.

10 Kane Computing, 7 Theatre Court, London Road, Northwich, Cheshire, CW9 5HB, UK.

11 B. W. Kernighan and D. M. Ritchie, *The C Programming Language, Second Edition*, Prentice-Hall, 1988.

12 3L Ltd., 86-92 Causewayside, Edinburgh, EH9 1PY, UK.

13 C. A. Poynton, *A Technical Introduction to Digital Video*, John Wiley and Sons, 1996.

00900
[per original]

The X-38 employs a "lifting body" concept originally developed by the U.S. Air Force's X-24A project in the mid-1960s. The concept uses the aerodynamic shape of the vehicle itself to generate the lift that a normal aircraft gets from its wings. This gives the X-38 vehicle good reentry maneuverability capabilities. More important, as a lifting body, the X-38 has excellent cross-range characteristics. These cross-range characteristics assure multiple opportunities for a dry terrain landing within the 9-hour lifetime of the vehicle consumables. The ability to return to earth quickly is very important and is a major advantage that the X-38 CRV has over the Russian Soyuz capsule, which is also under consideration for possible use as a CRV. Unfortunately, the Soyuz has two major drawbacks. The foremost is its inability to accommodate crewmembers that vary greatly in size, and the second is its limited crew carrying capacity, its not capable of carrying more than 3 crewmembers at a time. These issues caused concerns because the ISS will house crewmembers that vary greatly in size (5th percentile Asian female to 95th percentile U.S. male). Additionally, there are plans to have up to 7 crewmembers on the ISS at any time. Because of these concerns, an investigation into the development of an alternate method of returning crewmembers to earth was launched. This effort became known as the X-38 program. The X-38/CRV is being designed to accommodate the necessary range of crewmember sizes and have the capability of carrying 7 crewmembers at any time

V131 and V132 have composite fiberglass bodies and have undergone extensive testing during captive carry tests and free flight tests. During a captive carry test, a vehicle is attached to the wing of a B-52 and flown at different velocities and altitudes to collect data (Figure 1). During a free flight test the vehicle is carried to an altitude between 20k and 50k feet, under the wing of the B-52, and released. The vehicle flies "free" for several seconds before a large parafoil is deployed and used to return the vehicle safely to the ground.

V131 has undergone 7 captive carry tests and 2 free flight tests. V132 has undergone 1 captive carry and 1 free flight test. V133 is an atmospheric test vehicle similar to V132 and is currently being built. V201 is being built in-house at the Johnson Space Center and will be the first space-rated X-38 test vehicle. It will be taken into space on the Space Shuttle in November of 2000. Once in space, it will be taken out of Shuttle payload bay by the Remote Manipulator System and released. The X-38 will then run through its automated check out procedures and begin the de-orbit sequence. The vehicle will then enter earth's atmosphere and at an altitude of about 30k feet a large steerable parafoil, with active guidance from an on-board GPS receiver, will deploy and safely return the vehicle to the ground.

Figure 1: V131 during captive carry test 1.

The current X-38 CRV mission requirements include returning up to 7 crewmembers from the ISS safely to earth, have the ability to insure a dry terrain landing, and have enough cross-range to insure three landing opportunities in nine hours. This would be done in the event that any of the following situations arise: an ISS catastrophe, an emergency medical evacuation, or the Shuttle is unavailable to re-supply the ISS. Because we must design to a worst case scenario, a medical emergency where crewmembers are unable to pilot the vehicle back to earth, a fully autonomous vehicle must be built.

The basic assumption that a pilot is not necessary to return the CRV to earth meant that a forward-looking window was not required on the CRV. Although full autonomy is necessary for the medical evacuation scenario, keeping crewmembers in-the-loop to take care of unforeseen situations whenever possible is also a must. Synthetic environment technology is ideal for augmenting a crewmembers situational awareness and helping them to reselect a landing site or to fly the vehicle during the parafoil phase, when necessary. Additional software is being developed that allows crewmembers the ability to power subsystems on/off and more fully interact with several X-38 systems. We have been using our synthetic environment system to monitor flights, and to analyze/playback data during our V131 and V132 testing. In this role it acts as a tele-presence tool. To this end the LandForm Real-time 3-D Terrain Modeler, a commercial off the shelf (COTS) software package is being used. This product was selected because it met the above requirements. is very easy to use, and offers substantial cost and time savings.

00981

[per original]

The X-38 uses a large parafoil for the final landing phase. This parafoil is the subject of a significant engineering effort and considerable effort has been spent testing the parafoil system. Testing is done using large instrumented pallets attached to the parafoil. The pallets are released from the back of a C-130 aircraft and data on the aerodynamics, deployment sequence, and overall performance are recorded and closely analyzed. Early testing has yielded an ample amount of data which has been used to successfully build a parafoil system that has safely returned the V131 vehicle back to the ground during both free flights. Additional testing is being conducted to fine-tune the parafoil performance with the use of a remotely piloted vehicle, known as the buckeye. A pilot on the ground will fly the buckeye using visual feedback from one or more onboard video cameras. It is desirable to augment the pilot's view of the world with our system acting as a three-dimensional heads up display (HUD). In this way, information about landing zones and obstacles obscured from the camera could still be visible in our displays. Such tele-operation tools can considerably reduce the risks of remotely operating aircraft.

Initial tests with the product were very successful, and as astronauts came in contact with the system being developed, it became apparent that it would also serve well as a space-crew-training tool, and could considerably improve pilot situational awareness as a ground-based or onboard avionics display. However, for it to be used in these particular situations, it will need to be embedded into other applications, and not operate as a stand-alone program. Therefore, it would need to be accessible as a toolkit, which NASA engineers could use to augment any avionics software systems.

2. Requirements

Fundamentally the system must provide a real-time three-dimensional display of the environment, incorporating diverse terrain, navigation, and aircraft data. This display should be a natural perspective from a viewpoint controlled to six degrees of freedom (6 DOF). In most cases degrees of freedom applied to the viewpoint include latitude, longitude, altitude, pitch, heading and roll, versus time. Typically such data is obtained from an Embedded GPS Inertial Navigation Systems on board the aircraft and either used on-board, transmitted and viewed live, or recorded and replayed as a flight track at a later time. The camera modeled by the software must be a perspective camera that can be placed at any point in our 3-D virtual environment, and rotated about 3 axes to any orientation to simulate any viewpoint in which a real camera might be found. This 3-D synthetic vision of the world must also incorporate diverse elements including:

- land surface shape (topography),
- textures or draped imagery including digital maps,
- satellite and aerial imagery,
- geo-stationary objects like landing zones and obstacles,
- man-made or other transient objects, including aircraft, (we use the name *entities* for such objects)
- heads-up displays which project important information about the situation.

Figure 2: Parafoil deployed prior to landing.

Incorporating dynamic object entities into the scene is important for the X-38 so that the program could show the vehicle, the flight path (actual and ideal), as well as showing the parafoil and drogue shoot. The parafoil model is not only moving in real-time, but is changing shape as different control forces are applied. The ability to observe these effects in real-time is a requirement for flight testing, so entities must not only be controlled by 6 DOF, but it must be possible to incorporate a dynamically changing body shape model.

Simplicity of operation is a vitally important requirement for operation of a crew return vehicle. Most existing terrain software requires that expert users edit the terrain model for a given region of the world, and thus create the topography. The update rate of the 6 DOF viewpoint is up to 60 times per second, as is the update rate for entities moving in the virtual environment model for the virtual environment. Such a constraint is unacceptable for this application. As the X-38 might be compelled to begin its landing sequence from anywhere, it is not practical to have astronauts editing terrain models for a

virtual planet. Fortunately, LandForm accepts most common forms of terrain models, such as DTED, DEM, DTM and will automatically generate a land surface model for a given region of interest. The region of interest can be automatically moved by the program, based on the view position. Landform can automatically load files needed to make the terrain models. As a result, operation of the software can be automated to a very large extent, while providing greatly enhanced situation awareness. Figure 3 and Figure 4 are typical situation awareness displays for the X-38.


| 3 (a) | 3 (b) | 3 (c) |

Figure 3: These are typical out-the-window displays that have been prototyped for use on the X-38 program. In Figure 3(a) we have an out-the-window display that uses terrain elevation models and HUD symbology. In Figure 3(b) we have an out-the-window display created using high-resolution imagery data, a vehicle model, and HUD symbology. In Figure 3(c) we have an out-the-window display created using terrain elevation models, vehicle and parafoil models, and HUD symbology.

We are developing a "mobile cockpit" for use as a rapid development testbed for the synthetic environment system we are developing. The "mobile cockpit" is a 15 passenger van that has been outfitted with tinted windows to decrease light, a Global Positioning System, display computers, adjustable crew displays, hand controllers, a remote-controlled camera, an avionics rack for flight computers, and wireless headsets that allow the driver of the van to communicate with the individual handling the avionics systems and with crew members who lay supine in the back of the van. The result is a generic platform that may be used as a remote cockpit, as a rapid prototyping test bed, as a motion based simulator and as a vehicle for real-time flight following. Figure 5 shows the mobile cockpit avionics rack and its associated hardware components. Figure 6 shows the prototype mobile cockpit seats and display computers. The software being developed will be target to run on any Windows computer platform. The software should make use of 3-D accelerator hardware if available, but should not require it.


| 4(a) | 4(b) |

Figure 4: These are typical birds-eye-view displays. 4(a) is birds-eye-view display created using an aeronautical chart. 4(b) is birds-eye-view displays created using a high-resolution satellite image.

**Figure 5: Computers and GPS equipment used in the mobile cockpit.**

Figure 6: Mobile cockpit seats with display consoles.

3. Architecture

Our idea in approaching this work was that it should be possible to create a package or library that would encapsulate the easy-to-use LandForm Real-Time 3-D Terrain technology in programmer-accessible modules. If successful in our object-oriented design for this system, the package would expose only those methods or elements of importance to the user, and would hide those things which they did not need to worry about. This idea of *abstraction* is fundamental to maintaining interface simplicity.

The functional architecture, figure 7, was designed to achieve an optimal balance between power and simplicity. To this end the most obvious component encapsulates the LandForm 3-D Terrain display, herein called the LandView3D. This component uses the land surface model produced by the LandForm Server, and the viewpoint to render the 3D perspective. Camera model elements, such as field of view, are intrinsic to the LandView3D component. The LandForm Server is responsible to manage the terrain and overlay image data, flight track data, and time/event management provides this information to the views. A third component, the MapView provides a 2D parallel to the LandView3D. The MapView can be used for navigation, and to display the vehicle position in a traditional two-dimensional, North-up display, of predefined scale.


Figure 7: Basic architecture

153

00984

While the viewpoint server provides data for the camera and vehicle position, it can also be used to provide data on other objects (like aircraft) in the scene.

One of the key considerations for this system was the selection of a graphical API (Application Programming Interface) which would provide near-real-time 3-D rendering of the scene (including simulated land surface and vehicles). The OpenGL API was selected for this purpose, over alternatives like DirectX, for several reasons. First, having tested other APIs, OpenGL has the most reliable performance on a variety of graphics adapters and platforms. Second, it provided ample rendering speed, provided reasonable care was taken in programming the OCX controls and application. And third, it is distributed as a standard part of the Windows operating system and thus should be well supported over a period of years by the operating system vendor.

4. Implementation

The first step was to determine whether the ActiveX API would allow us to create an OpenGL display within a control, and whether such an implementation would be as fast, in terms of rendering speed, as LandForm. If so, then ActiveX would appear to be the logical choice for implementation. To test this idea, we created an ActiveX control that contains the LandForm 3D scene renderer, and the LandForm Server component described above. (This is the LandView3D control we discussed earlier).

We tested the rendering speed and found it was comparable to the stand-alone LandForm program. By achieving 20 frames per second on a modestly equipped machine, the LandView3D control provides more than adequate rendering performance. This key data point cleared the way for full implementation using the ActiveX paradigm. ActiveX is a form of the Component Object Module (COM) architecture, which offers excellent interoperability of libraries between programming languages and operating environments.

In parallel with the LandView3D control, we began the development of a 2-D map display that would function similarly to the right-hand map view in LandForm. This was relatively straightforward, and was also implemented using the Active X paradigm. One part of the development that was not trivial was the creation of a transparent control to be overlaid on the map so that other data could be displayed, such as a compass, or windsock. This required some research and experimentation before a truly successful method was developed.

The LandForm Server, which contains the core of LandForm's capability had to be implemented in a programmably accessible form. While it would be simplest to create an object as a dynamic link library, we felt interoperability was better served by creating a COM version of this object. The logical choice here was as an ActiveX. Finally, a sample application was created which combined these basic capabilities. To this end we used Microsoft Visual C++ to develop a dialog based Windows application containing the new sample tools and to serve as a template for developers to model their own applications upon. Figure 8 shows a sample application.

5. Application: A 3-D Heads Up Display

One powerful application of LandForm is to combine simulated LandForm 3-D scenery with live video, to create an enhanced situational awareness display. For pilots of both full scale and remotely piloted aircraft, such a display will provide a view of the surroundings which includes live video, and enhanced with outlines of terrain,


Figure 8: Sample application with LandForm 3D view control.

other aircraft, landing zones, targets or other objects of importance. Furthermore because the terrain portion of the display is generated from digital data, it is not subject to the limitations of visibility inherent to video. While darkness, terrain occlusion, smoke, fog, and haze all impact the video, the overlays will be unobstructed. Figure 9 expresses the fundamental concept. A computer running the LandForm ActiveX control utilizing the current vehicle position models the real video camera field of view and orientation.

```
                         ┌──────────────┐
                         │ LandForm     │
                         │ computer     │
                         │ graphics     │
                         │ output       │
                         └──────────────┘
                                │
                                ▼
┌──────────────┐       ┌──────────────┐       ┌──────────────┐
│ Video        │       │ Video Mixer  │       │ LandForm     │
│ Camera       │  ──▶  │ (Chromakey)  │  ──▶  │ 3-D scene    │
│ Signal       │       │              │       │ overlaid     │
└──────────────┘       └──────────────┘       │ on video.    │
                                               └──────────────┘
```

Figure 9: Enhanced situational awareness is achieved with the combination of LandForm 3-D scenery and live video.

The real camera is mounted at a known orientation on the vehicle, thus the video from the camera and the LandForm simulated scene constitute parallel views of the world – one based upon photons at the sensor, the other based upon the LandForm database. LandForm is then configured to render wire-frame rather than solid surfaces, which may then be overlaid upon the real-time video. So if a mountain appears in the LandForm terrain database, in front of the camera it should be rendered in the same place and orientation in the real video. Indeed it should overlay as precisely upon the live mountain scene as the data permit. Likewise if a landing zone is indicated in the scene it should appear at just the same location as in the video.

Figures 10 and 11 show a parallel view of the world from a video camera's perspective and LandForm's simulated scene respectively. Figure 10 is a video digital image of the Mt. Jacinto area in California. Figure 11 shows the same area rendered by LandForm based on the field of view of the camera and camera viewpoint.

Figure 10: Digital image of Mt. Jacinto, Ca.

155

00986

Figure 11: LandForm simulation of the terrain from the camera and viewpoint for the photo above.

6. Results

We believe we have demonstrated the utility of a general purpose 3D terrain-enabled software display toolkit for flight guidance applications, both for operation and teleoperation of aircraft and spacecraft. It is clear that even PC computers may have adequate performance to provide a smooth real-time 3D display of the terrain and aircraft in flight. One of the most important uses of this technology will be as a 3D heads up display (HUD), and in the case of the X-38 program to improve a pilot's situation awareness.

Before a tool of this type can be used in operational spacecraft and aircraft, testing must be performed to validate the limits of performance of the software. We think that this system offers a substantial step forward in flight guidance via a virtual environment. We are also interested in the opinions of others. Free downloadable sample versions of the software can be obtained from www.landform.com/AFVT.htm on the World Wide Web. The LandForm plug-ins developed for the X-38 program can be acquired by contacting fdelgado@ems.jsc.nasa.gov.

7. Acknowledgements

This work was sponsored by NASA Contract NAS9-99032 and by Rapid Imaging Software, Inc. Assistance and technical insight into COM, Active X, and Windows programming was provided by Linda Moreland (NASA/JSC) and Steven Robinson (Panther Software), thank you both. Limited programming support was provided by Nicolas Graf (NASA/JSC), Antoine Dumurgier (European Space Agency), Nicolas Pen (European Space Agency), and Fabrice Cinquetti (European Space Agency) during the development of the HUD symbology.

8. References:

1. F.J. Delgado, "Accurate Determination of Flight Control Airdata Parameters Using Artificial Neural Networks and the X-38 Flush Airdata System" *Proceedings of the Texas Systems Day, 1997.*
2. J. F. Muratore and C. S. Iacomini, "Parafoil Flight Test of X-38 Prototype Crew Return Vehicle Yields Improved Instrumentation and Techniques", *Journal of International Flight Test and Evaluation Association,* pp 19-24, June/July 1998, Volume 19, Number 2.
3. M. F. Abernathy and S. Shaw, "Integrating Geographic Information in VRML", *Proceedings of the Third Symposium on Virtual Reality Modeling Language,* VRML 98.

00987